UBC Social Ecological Economic Development Studies (SEEDS) Sustainability Program

Student Research Report

#### **Corridor Redesign of Chancellor Boulevard - Team 22**

#### Bain Konway, Brad Krahn, Stuart Martinson, Megan Norwick, Katrina Ong, Chris Pertch

#### **University of British Columbia**

#### **CIVL 445**

#### Themes: Transportation, Community, Land

#### April 9, 2018

Disclaimer: "UBC SEEDS Sustainability Program provides students with the opportunity to share the findings of their studies, as well as their opinions, conclusions and recommendations with the UBC community. The reader should bear in mind that this is a student research project/report and is not an official document of UBC. Furthermore, readers should bear in mind that these reports may not reflect the current status of activities at UBC. We urge you to contact the research persons mentioned in a report or the SEEDS Sustainability Program representative about the current status of the subject matter of a project/report".




 $12324~70^{\mbox{\tiny th}}$  Street, Vancouver, BC

Submitted: Prepared by: Prepared for: April 10, 2018 Campus Consulting Ltd. UBC Campus and Community Planning

# **Corridor Redesign of Chancellor Boulevard**

Detailed Design Report





MAXIMUM





## Executive Summary

Chancellor Boulevard is one of four roads accessing the University of British Columbia's Point Grey campus. The corridor currently experiences heavy vehicle traffic at two peak times per day with drivers routinely exceeding the posted speed of 60 km/hr. In the current design, cyclists must share the road with vehicles as there is no separated or designated bike lane.

Campus Consulting Ltd. was retained to complete both a preliminary and detailed design. The detailed design report herein includes: a grade separated pedestrian underpass, a two-lane road (without a median), a roundabout to slow traffic, and an infiltration swale separating the multi-use path from the road to infiltrate road runoff.

The Corridor Redesign of Chancellor Boulevard provides an opportunity to address some of these key issues as well as other identified issues including stormwater management, environmental protection, geotechnical concerns, and stakeholder concerns. The objectives governing the redesign process include:

- meeting all future transportation demands,
- prioritizing buses, cyclists, and pedestrians and ensuring the safety of all road users,
- avoiding negatively impacting Pacific Spirit Park and the habitats it provides,
- accommodating and improving drainage, and
- minimizing costs and optimizing the construction schedule.

The updated cost of the design is \$3.86 million, an increase from \$3.43 million as estimated during the preliminary design phase.



# Contents

| 1. Project Understanding |     |          |  |
|--------------------------|-----|----------|--|
|                          | 1.1 | . De     | sign Objectives2                                   |
|                          | 1.2 | . Ke     | y Issues2  |
|                          | 1   | L.2.1.   | Design Speed and Driver Speed2                     |
|                          | 1   | L.2.2.   | Pedestrian Safety3                                 |
|                          | 1   | L.2.3.   | Bicycle Safety3                                    |
|                          | 1   | L.2.4.   | Preservation and Improvement of Local Environment4 |
|                          | 1   | L.2.5.   | Drainage Improvements4                             |
|                          | 1   | l.1.1.   | Stakeholder Concerns4                              |
|                          | 1.3 | . Ta     | sk Register5                                       |
| 2.                       | E   | Existing | conditions7  |
|                          | 2.1 | . Tra    | affic Analysis7                                    |
|                          | 2   | 2.1.1.   | Existing Conditions7                               |
|                          | 2   | 2.1.2.   | Results  |
|                          | 2   | 2.1.3.   | Design Solutions9                                  |
|                          | 2.2 | . En     | vironmental Assessment9                            |
|                          | 2   | 2.2.1.   | Background9  |
|                          | 2   | 2.2.2.   | Assessment Methods9                                |
|                          | 2   | 2.2.3.   | Results  |
|                          | 2   | 2.2.4.   | Recommendations11                                  |
|                          | 2.3 | . Ge     | otechnical Analysis                                |
|                          | 2   | 2.3.1.   | General Soil Conditions12                          |
|                          | 2   | 2.3.2.   | Pavement Condition                                 |
|                          | 2   | 2.3.3.   | Recommendations14                                  |
|                          | 2.4 | . Sto    | ormwater Assessment                                |
|                          | 2   | 2.4.1.   | Existing Conditions15                              |
|                          | 2   | 2.4.2.   | Climate Change Considerations16                    |
|                          | 2   | 2.4.3.   | Recommendations:                                   |



|    | 2.5. Stakeholder Engagement |        | eholder Engagement                 |
|----|-----------------------------|--------|------------------------------------|
| 3. | Deta                        | ailed  | Design                             |
|    | 3.1.                        | Pede   | estrian Underpass                  |
|    | 3.2.                        | Road   | dway                               |
|    | 3.2.                        | 1.     | Design Speed and Alignment         |
|    | 3.2.                        | 2.     | Intersection Design                |
|    | 3.2.                        | 3.     | Pedestrian and Bike Improvements19 |
|    | 3.2.4                       | 4.     | Paint markings and signage20       |
|    | 3.3.                        | Stor   | mwater Management                  |
| 4. | Con                         | struc  | tion Management                    |
|    | 4.1.                        | Cons   | struction Specifications           |
|    | 4.2.                        | Cons   | struction Sequencing               |
|    | 4.3.                        | Anti   | cipated Issues                     |
|    | 4.4.                        | Cons   | struction Cost                     |
| 5. | Ope                         | ratio  | ns and Maintenance                 |
|    | 5.1.                        | Min    | or Operations and Maintenance25    |
|    | 5.2.                        | Majo   | or Operations and Maintenance27    |
| 6. | Con                         | clusic | on28                               |
| 7. | Soft                        | ware   | & References                       |
|    | 7.1.                        | Soft   | ware                               |
|    | 7.1.                        | 1.     | Civil3D                            |
|    | 7.1.                        | 2.     | PCSWMM                             |
|    | 7.1.                        | 3.     | ETCulvert                          |
|    | 7.1.4                       | 4.     | Synchro 6 plus SimTraffic          |
|    | 7.1.                        | 5.     | Sidra Intersection 7.0             |
|    | 7.2.                        | Refe   | rences                             |



# List of Figures

| Figure 1-1: Location of project  | 1  |
|--|----|
| Figure 1-2: Typical section of roadway along Chancellor Boulevard                              | 2  |
| Figure 1-3: A jaywalking desire path has formed to connect two trailheads on opposite sides of |    |
| Chancellor Boulevard   | 3  |
| Figure 1-4: Bicyclist choose to ride on Chancellor Boulevard despite the lack of bike lanes    | 3  |
| Figure 1-5: Evidence of beaver habitation in the stream adjacent to University Hill Elementary | 4  |
| Figure 1-6: UBC Endowment Lands neighborhood on west end of project                            | 4  |
| Figure 2-1: Culvert outlet in riparian zone adjacent to Chancellor Blvd                        | 15 |
| Figure 4-1 Schematic Construction Schedule   | 23 |



# List of Tables

| Table 2-1: Unsafe Traffic Occurrences During Peak Hour Flow                         | 7  |
|---|----|
| Table 2-2: Peak Hour Traffic Volumes at Intersection of Chancellor Blvd & Hamber Rd | 8  |
| Table 2-3: Summary of Existing Intersection Performance at Present Day              | 8  |
| Table 2-4: Listed species within project area                                       | 11 |
| Table 2-5: Point Grey peninsula stratigraphy  | 12 |
| Table 2-6: Pavement condition summary   | 14 |
| Table 3-3-1: Minimum Design Values  | 19 |
| Table 3-2 Roundabout Geometry   | 19 |
| Table 5-1 Minor Operations and Maintenance Line Items                               | 26 |
| Table 5-2 Minor Operations and Maintenance Costs                                    | 26 |
| Table 5-3 Major Operations and Maintenance Line Items                               | 27 |



# 1. Project Understanding

Campus Consulting Ltd. has been retained by UBC Campus Community Planning to provide detailed design engineering services and service-life maintenance planning for the Chancellor Boulevard Redesign Project on the UBC Vancouver campus. This Detailed Design Report for the Chancellor Boulevard Redesign Project follows the previously issued Preliminary Design Report (November 28, 2017).

Chancellor Boulevard, which is an arterial road extending from West 4th Avenue and one of four gateways onto the UBC campus (*Figure 1-1*), is in need of a redesign to increase mode share along the 1.8 km corridor to give priority to pedestrians, cyclists, and buses while at the same time reducing traffic speed to 50km/h to increase safety for road users. The corridor is in need of a grade separated pedestrian crossing to provide a safe crossing for pedestrians and cyclists accessing University Hill Elementary School and the trails connecting Pacific Spirit Park.



Figure 1-1: Location of project



# 1.1. Design Objectives

UBC Campus Community Planning has prioritized the following design objectives:

- meet all future transportation demands
- prioritize buses, cyclists, and pedestrians and ensure the safety of all road users
- avoid impacting Pacific Spirit Park and the habitats it provides
- accommodate and improve drainage
- minimize costs and optimize the construction schedule

Each of these objectives were integral during the design process and have been met through various design features.

### 1.2. Key Issues

#### 1.2.1. Design Speed and Driver Speed

The posted speed limit in the corridor is 60km/hr (*Figure 1-2*), but typical traffic speeds exceed this speed limit. A reason for this is the road design - the road is currently a four-lane divided highway with gentle horizontal and vertical curves and long sight distances, which encourages speed along this section of the corridor, especially after the relatively tight sections of road that precede and follow.



Figure 1-2: Typical section of roadway along Chancellor Boulevard





Figure 1-3: A jaywalking desire path has formed to connect two trailheads on opposite sides of Chancellor Boulevard

discourages cyclists from using it.

#### 1.2.2. Pedestrian Safety

University Hill Elementary School and Pacific Spirit Park are located along the corridor, so there are many pedestrians using the corridor. Both driver speed and lack of pedestrian crossings presents a pedestrian safety issue. Currently, the corridor only has one pedestrian-controlled crossing at the elementary school but no other protected crossings. Several trails in Pacific Spirit Park are bisected by the corridor including Salish Trail, and Pioneer Trail. Despite driver speeds and a lack of protected crossings, there is evidence of pedestrian and bicycle crossings near the Pacific Spirit Park trailheads that exit along the corridor, as seen in *Figure 1-3*. There is one existing multi-use path along the south side of the corridor but it is in disrepair in some areas, making the pathway less navigable for some users, and

#### 1.2.3. Bicycle Safety

This stretch of Chancellor Boulevard does not currently provide bike lanes even though West 4th east of Drummond road and Chancellor boulevard west of Acadia Road both include at grade bike lanes (*Figure 1-4*). The lack of bike lanes means cyclists are forced to share the road with cars travelling above the speed limit, or ride on the poorly maintained multi-use path, which can interfere with pedestrians, drivers, and transit.



*Figure 1-4: Bicyclist choose to ride on Chancellor Boulevard despite the lack of bike lanes* 





# Figure 1-5: Evidence of beaver habitation in the stream adjacent to University Hill Elementary

# 1.2.4. Preservation and Improvement of Local Environment

Chancellor Boulevard bisects the northern part of Pacific Spirit Park, a 763 hectare nature preserve with a large variety of ecosystems including wetlands, meadows, and dense coastal forest (*Figure 1-5*). Development throughout the park is minimal to keep it as natural as possible. Any development nearby has the potential to impact these precious ecosystems, which is why the effects due to the project will be considered and carefully mitigated.

#### 1.2.5. Drainage Improvements

Existing drainage management involves both built and natural drainage networks including roadside ditches, stormwater sewers, culverts, and three natural catchments that drain towards the ocean. The existing drainage is

performing adequately, but improvements to stormwater quality and volume reduction could be made in keeping with UBC's Integrated Stormwater Management Plan.

#### 1.1.1. Stakeholder Concerns

Chancellor Boulevard connects many of UBC's surrounding neighbourhood's and community services and as such, the project requires input from many stakeholder groups. Stakeholder consultation is critical to the success of the project to ensure the redesign encompasses their vision for the corridor. Much of the feedback collected to date was incorporated in the detailed design and will continue to be considered throughout the next phases of the project (as seen in *Figure 1-6*).



*Figure 1-6: UBC Endowment Lands neighborhood on west end of project* 



# 1.3. Task Register

|                       | Task              | Person           |
|-----------------------|-------------------|------------------|
|                       |                   | Responsible      |
| SEED Cover            |                   | Megan            |
|                       |                   | Norwick          |
| Letter of Transmittal |                   | Megan            |
|                       |                   | Norwick          |
| Executive Summary     |                   | Stuart           |
|                       |                   | Martinson        |
| Table of contents     |                   | Megan<br>Norwick |
| Brainet Understanding |                   | Megan            |
| Project Understanding |                   | Norwick          |
|                       | Introduction      | Megan            |
|                       | Introduction      | Norwick          |
|                       | Design Objectives | Megan            |
|                       | 20019/1 00/001/00 | Norwick          |
|                       | Key Issues        | Megan            |
|                       |                   | Norwick          |
|                       | Design Criteria   | Megan            |
|                       | -                 | Norwick          |
| Existing Conditions   |                   |                  |
|                       | Traffic Analysis  | Chris            |
|                       |                   | Pertch           |
|                       | Environmental     | Megan            |
|                       | Assessment        | Norwick          |
|                       | Stormwater        | Stuart/Meg       |
|                       | Assessment        | an               |
|                       | Stakeholder       | Katrina          |
|                       | Engagement        | Ong              |
|                       | Geotechnical      | Stuart           |
|                       | Analysis          | Martinson        |
|                       | Pavement          | Brad Krahn       |
|                       | Condition         |                  |
|                       | General Soil      | Stuart           |
|                       | Conditions        | Martinson        |
| Detailed Design       | Conditiono        |                  |
|                       | Dodoctrion        | Stuart           |
|                       | Pedestrian        | Martinson        |
|                       | Underpass         | Bain             |
|                       | Roadway           | Bain<br>Konway   |
|                       | Stormwater        | Stuart/Meg       |
|                       | Management        | an               |
|                       | Construction      | Chris            |
|                       |                   | Pertch           |
|                       | Specifications    |                  |
|                       | Construction      | Chris<br>Pertch  |
|                       | Sequence          | FEIGH            |



|  | Anticipated Issues            | Chris<br>Pertch     |
|--|-------------------------------|---------------------|
|  | Construction Cost             | Chris<br>Pertch     |
|  | Operations and<br>Maintenance | Chris<br>Pertch     |
| Conclusion   |                               | Megan<br>Norwick    |
| Software & References  |                               | All                 |
| Appendix A: Species List   |                               | Megan<br>Norwick    |
| Appendix B: Underpass Sample Calculations                                  |                               | Brad Krahn          |
| Appendix C: 2016 MOTI Standards for Highway<br>Construction Specifications |                               | Chris<br>Pertch     |
| Appendix D: Detailed Construction Schedule                                 |                               | Chris<br>Pertch     |
| Appendix E: Updated Cost Estimate  |                               | Chris<br>Pertch     |
| Drawing Package  |                               | Bain and<br>Katrina |



# 2. Existing Conditions

## 2.1. Traffic Analysis

A detailed traffic analysis was conducted to identify traffic issues the corridor was experiencing and the current level of service for the intersection. The analysis included a traffic count, site observations, and computer modelling, which identified areas of improvement and provides suggested techniques for mitigating identified issues.

#### 2.1.1. Existing Conditions

It was observed that the corridor operates efficiently and is appropriately sized during peak hour traffic, but it is grossly overdesigned for off-peak hours. This type of overdesign can give rise to issues such as speeding and driver complacency. Site visits were undertaken to provide general observations as well as to conduct a traffic count during peak hours. Several observations of traffic concerns include:

- Excessive speeding
- Illegal U-Turns at the intersection of Hamber Road and Chancellor Boulevard
- Unsafe vehicle maneuvers around cyclists using the roadway
- Pedestrian jay walking

The traffic count, which was completed on September 28th, 2017, is summarized in Table 2-1.

| Table 2-1: Unsaf | e Traffic Occurrences | During Peak Hour Flow |
|------------------|-----------------------|-----------------------|
|------------------|-----------------------|-----------------------|

| Unsafe Traffic Occurrences During Peak Hour Flow |                 |                 |              |             |  |
|--|-----------------|-----------------|--------------|-------------|--|
|  | Excessive Speed | Illegal U-Turns | Unsafe Turns | Jay-Walking |  |
| Instances per                                    | 12              | 6               | 11           | 2           |  |
| Hour <sup>1</sup>                                |                 |                 |              |             |  |

<sup>1</sup> Only includes instances observed in direct vicinity of Hamber & Chancellor intersection. Actual number of instances along entire length of corridor may be higher. Instances of unsafe behaviour were assessed visually.

During the count, it was revealed that a regular amount of heavy vehicles (buses, trucks, etc.) were observed and as such our analysis accounts for 5% heavy vehicles by traffic volume. Typical analysis uses a 1-2% annual traffic growth rate, however, because both UBC and the City of Vancouver are undertaking policies to reduce personal vehicle use, current traffic levels are more likely to decrease in



coming years [1] [2]. Therefore, modelling uses present day values for all design analysis. The peak hour volume results used for traffic analysis are summarized in *Table 2-2* below.

| Present Day Peak Hour Summary (All Vehicles) |                              |       |                              |      |                         |       |                               |  |
|--|------------------------------|-------|------------------------------|------|-------------------------|-------|-------------------------------|--|
|  | Chancellor Blvd<br>Eastbound |       | Chancellor Blvd<br>Westbound |      | Hamber Rd<br>Southbound |       |                               |  |
|  | Through                      | Right | Through                      | Left | Left                    | Right | Total<br>Peak Hour<br>Traffic |  |
| AM Peak<br>Hour                              | 756                          | 70    | 210                          | 103  | 46                      | 91    | 1276                          |  |

Table 2-2: Peak Hour Traffic Volumes at Intersection of Chancellor Blvd & Hamber Rd

#### 2.1.2. Results

Synchro 6 was used to model the existing intersection under existing conditions. The Level of Service (LOS) and average delay for each approach was analyzed, as well as an overall rating determined for the intersection. These conditions are summarized in *Table 2-3* below.

Table 2-3: Summary of Existing Intersection Performance at Present Day

| Existing Intersection Condtions |                              |                              |                         |  |  |
|---------------------------------|------------------------------|------------------------------|-------------------------|--|--|
|                                 | Chancellor Blvd<br>Westbound | Chancellor Blvd<br>Eastbound | Hamber Rd<br>Southbound |  |  |
|                                 | Thru/RT                      | Thru/LT                      | LT/RT                   |  |  |
| LOS                             | А                            | А                            | F                       |  |  |
| Delay (Sec)                     | 0                            | 5.8 (Thru), 3.1 (LT)         | 143.6                   |  |  |
| Overall Intersection            | D                            |                              |                         |  |  |
| LOS                             |                              |                              |                         |  |  |
| Overall Intersection            | 20.0                         |                              |                         |  |  |
| Delay (Sec)                     |                              |                              |                         |  |  |

The intersection currently operates under an acceptable LOS, except for left turning traffic leaving the elementary school from Hamber Road which has a very poor level of service. This result agrees with observations made during the traffic count. Under peak traffic, left-turns from Hamber are often forced to wait until pedestrians trigger the crosswalk on Chancellor. Due to the long wait, drivers often choose to turn right onto Chancellor boulevard and perform illegal U-turns at Acadia Road to the west in order to shorten their wait.



#### 2.1.3. Design Solutions

The following solutions, guided by NACTO's Urban Street Design Guide [3], have been designed to alleviate the above noted concerns and include:

- narrowing the roadway
- removing the boulevard to create a 2-way street
- including bike lanes along the corridor
- visually narrowing the roadway through tree planting and other foliage
- adding pedestrian crosswalks at the three major trail heads into Pacific Spirit Park

To address the poor level of service for left-turning traffic from Hamber Road, a roundabout has been designed to better accommodate school traffic during the peak morning hours and double as a traffic calming feature.

### 2.2. Environmental Assessment

An Environmental Assessment (EA) was conducted to identify environmentally sensitive areas and take inventory of all Species At Risk within the project area. The findings of the EA, the identified regulatory requirements, and implemented mitigation measures are below.

#### 2.2.1. Background

Chancellor Boulevard bisects Pacific Spirit Park, a 874 hectare nature reserve owned by the government of British Columbia, within the University Endowment Lands. The park consists of several ecologically important ecosystems including mature forest, young forest, wetlands and riparian habitat. Salish (Acadia) Creek and Spanish Banks Creek provide spawning and rearing habitat for Chum and Coho salmon, after restoration efforts were recently made to return them to salmon-bearing status, and therefore are of particular importance due to their proximity to the project.

#### 2.2.2. Assessment Methods

A desktop study and literature review was conducted using the following resources:

- Government of Canada Habitat Stewardship Program brochure
- BC Species and Ecosystems Explorer



- BC Conservation Data Centre database (CDC)
- Metro Vancouver Sensitive Ecosystem Inventory

Using the CDC database, results for flora and fauna were compiled and sorted based on their red, blue, or yellow BC listing (Appendix #). The rankings, described below, highlight the risk-status of wildlife and plant species as well as natural plant communities in BC:

- Red Extirpated (X), Endangered (E), or Threatened (T) in BC
- Blue not immediately threatened but of Special Concern in BC
- Yellow Not at Risk in BC

These designations are used in this report to indicate the status of species and ecosystems observed with respect to the provincial listings of species at risk. A site survey was conducted on October 19, 2017 to field truth sensitive areas found during the desktop study, with a specific focus on riparian areas and streams. Regulatory considerations for the project were identified as follows:

- Federal
  - Species at Risk Act (SARA)
  - o Fisheries Act
- Provincial
  - BC Wildlife Act
  - Riparian Areas Regulation (RAR)
- University Endowment Lands (UEL)
  - Official Community Plan
  - o Land Use, Building and Community Administration Bylaw
  - Works and Services Bylaw
  - University Endowment Land Act

#### 2.2.3. Results

The Sensitive Ecosystem Inventory revealed that the project area is within an area generally considered as sensitive with the following sensitive ecosystems being identified: mature forest, young forest, wetlands and riparian habitat. Identification of environmentally sensitive areas allows for the creation of action plans to be implemented that help maintain and improve those ecosystems that provide valuable



ecosystem services. The protection of Salish (Acadia) Creek and Spanish Banks Creek, which were identified as being salmon-bearing, supports Metro Vancouver's long-term action plan for supporting salmon in the cities.

Results from the CDC database search results are provided in *Appendix H*. A summary of the number of flora and fauna species returned in the database search is presented below in *Table 2-4*.

|        | Amphibian /<br>Reptile | Bird | Invertebrate | Mammal | Plant | Fish |
|--------|------------------------|------|--------------|--------|-------|------|
| Red    | 3                      | 2    | 5            | 1      | 1     | 3    |
| Blue   | 1                      | 4    | -            | -      | 2     | -    |
| Yellow | 1                      | -    | -            | 1      | -     | -    |

Table 2-4: Listed species within project area

No active raptor or migratory bird nests were observed during the site reconnaissance survey, nor were any inactive nests observed. A beaver dam was noted near the southern end of Salish Creek, though it appeared it had previously been altered to allow for drainage with a small, metal culvert.

#### 2.2.4. Recommendations

Environmental recommendations fall into two categories: protection of salmon-bearing streams and protection of species at risk. The proximity of salmon-bearing streams will require additional mitigation measures during construction to protect the streams from sediment runoff but the project also provides an opportunity to improve existing stream conditions by improving water quality. An Environmental Management Plan (EMP) will be prepared prior to construction, which will include an Erosion and Sediment Control (ESC) Plan outlining key mitigations to implement during construction to protect nearby drainages. In addition, green stormwater infrastructure could help improve water quality by filtering all road runoff prior to it entering the streams.

Several red- and blue- listed flora and fauna were identified. Of those species identified, those considered to be likely occurring within the project area, based on habitat preference, were investigated further and mitigations for potential effects were focused on these species. Although construction activities will not directly interact with riparian habitat, relocation of some amphibian, invertebrate and small mammal species may be required in areas peripheral to the nearby streams if construction



activities have the potential to cause disturbance. The necessary wildlife handling and salvage permits would be obtained and any relocations would be completed by a Qualified Environmental Professional.

# 2.3. Geotechnical Analysis

A geotechnical study was conducted which showed that Point Grey is comprised of fluvial sedimentary deposits formed in a large delta between 50,000 and 20,000 years ago by a forebear of the Fraser River. The area was previously glaciated and the land that is now the peninsula was below sea level. After glacial retreat, the soil rebounded to its current elevation, approximately 60 metres above sea level.

#### 2.3.1. General Soil Conditions

Stratigraphy remains consistent across Point Grey peninsula for the most part, though the thicknesses of the strata vary. These strata are tabulated below in *Table 2-5*.

| Elevation (m ASL) | Stratum             | Description   |
|-------------------|---------------------|---|
| 68 - 69           | Capilano Sediments  | Beach Gravels and/or glaciomarine silt to clay loam |
| 65 – 68           | Vashon Drift        | Sandy, loamy lodgement till                         |
| 20 - 65           | Quadra Sand Unit Q1 | Fine to coarse sand, with minor silt and gravel     |
| 12 – 20           | Quadra Sand Unit Q2 | Interbedded silt, fine sand, and minor peat         |
| 10 – 12           | Quadra Sand Unit Q1 | Fine to coarse sand, with minor silt and gravel     |
| 3 - 10            | Quadra Sand Unit Q2 | Interbedded silt, fine sand, and minor peat         |
| 0 - 3             | Quadra Sand Unit Q1 | Fine to coarse sand, with minor silt and gravel     |

Table 2-5: Point Grey peninsula stratigraphy

The Vashon Drift stratum underlying the site is less permeable than the layers above and below it, and it undulates and varies in thickness. Water that infiltrates the surface layer perches on top of it and ultimately runs laterally to the cliffs on the edge of the peninsula where causes mass wasting and erosion. In locations where groundwater cannot reach the cliffs, it accumulates and slowly percolates into the Vashon Drift. Evidence of this is seen on the surface in the form of bogs. The Quadra Sand Unit Q1 is significantly more permeable than both the overlying till and the underlying Quadra Sand Unit Q2.



This layer is hence called the Upper Aquifer. The Quadra Sand Unit Q2 is an aquitard that transmits accumulating groundwater laterally where it seeps out of the cliffs. Groundwater that seeps through the aquitard enters the Lower Aquifer, where it again accumulates over the lower layer of Quadra Sand Unit Q1. Water that runs laterally seeps out of the base of the Point Grey Cliffs. As development on the peninsula has increased, so too has the ratio of impervious to pervious ground. This has forced infiltration to increase in the remaining pervious areas, ultimately leading to increased seepage at certain locations on the cliffs which has decreased slope stability and increased erosion.

#### 2.3.2. Pavement Condition

Cracking along the corridor was observed but no settlement or rutting of the roadway was observed, indicating that the road base is in good condition. The current pavement surface conditions are drivable but will worsen over time due to heavy vehicle weight. It is recommended to use a combination of mill and overlay, as well as repaying select areas to improve roadway safety and road user comfort.

The main road section between Hamber Road and Drummond drive could be milled and overlain, while the intersections of Hamber Road and Drummond Drive require complete removal and pavement replacement due to extensive cracking of pavement. This will ensure the best quality of road surface along Chancellor Boulevard for safety and comfort of road users. *Table 2-6* summarizes the existing road conditions.



#### Table 2-6: Pavement condition summary

| Location                     | Condition  | Recommended<br>Construction<br>Method |
|------------------------------|--|---------------------------------------|
| Hamber Rd. Intersection      | <ul> <li>Longitudinal Wheel Path Cracking (LWP):<br/>moderate</li> <li>Alligator Cracking (AC): moderate</li> <li>General: poor condition, minor potholes<br/>beginning</li> </ul>                             | Full-depth<br>reconstruction          |
| Westbound                    | <ul> <li>Longitudinal Wheel Path Cracking (LWP):<br/>low to moderate</li> <li>Alligator Cracking (AC): moderate</li> <li>General: fair condition, no rutting or<br/>potholes</li> </ul>                        | Mill and overlay                      |
| Eastbound                    | <ul> <li>Longitudinal Wheel Path Cracking (LWP):<br/>low to moderate</li> <li>Alligator Cracking (AC): moderate</li> <li>General: fair condition, no rutting or<br/>potholes, Right lane resurfaced</li> </ul> | Mill and overlay                      |
| Drummond Dr.<br>Intersection | <ul> <li>Longitudinal Wheel Path Cracking (LWP):<br/>moderate</li> <li>Alligator Cracking (AC): moderate</li> <li>General: poor condition, minor potholes<br/>beginning</li> </ul>                             | Full-depth<br>reconstruction          |

#### 2.3.3. Recommendations

The hydrogeology of the University of British Columbia's Point Grey campus has been well researched, and from this several recommendations have been made to guide safe development on campus. Some of these recommendations are applicable to the redesign of Chancellor Boulevard, especially the design of the tunnel and utility trenches. Past reports recommend that:

- Building and foundation trenches should be sealed, and perimeter drainage should be piped to storm drains
- Service trenches should have diversion barriers with diversion drains, to prevent the trenches from acting as conduits for groundwater

The recommendations above should be followed closely, and a monitoring regime should be implemented to ensure that no ill effects arise as a result of increased infiltration along the road



corridor. Dewatering wells have been drilled near the cliffs on UBC's campus with some success and, if necessary, more may be drilled to mitigate new problems.

In addition to the above recommendations, it is essential that a thorough geotechnical investigation and site characterization specific to this site take place. At least one borehole investigation should take place at the location of the proposed tunnel, and boreholes and surveying will be necessary along the length of the corridor to determine the localized soil profile in order to minimize the amount of full depth reconstruction required.

### 2.4. Stormwater Assessment

#### 2.4.1. Existing Conditions

The corridor runs through three catchments. In the current design, all but a very small portion of road runoff is discharged untreated into four outfalls in the Spanish, Canyon, and Salish (also known as Acadia) Creeks in Pacific Spirit Park. The remainder flows overland into a ditch on the Northside of Chancellor Blvd. where it is conveyed to Spanish Creek. In a recent investigation, sampling of the levels of aluminum, copper, manganese, and zinc, metals present were measured in the creeks and have been shown to exceed guidelines. The salmon populations in these creeks were thought to have been wiped out, but salmon have been observed recently in both Spanish and Salish Creeks in addition to the populations of resident trout (Figure 2-1).



Figure 2-1: Culvert outlet in riparian zone adjacent to Chancellor Blvd.



#### 2.4.2. Climate Change Considerations

Intensity-Duration Frequency (IDF) curves are the result of analysis of extreme precipitation events over a period long enough to be statistically significant and form the basis for the design of stormwater management infrastructure such as culverts and drain pipes. These IDF curves are based on historic data, but as the climate changes, so do the patterns of local rainfall. Because of this, efforts are being made to update current IDF curves. This is important because if municipal infrastructure is designed using underestimated rainfall, it will not be able to handle increased future stormwater loads. Conversely, it is also important to be able to predict future droughts. A study initiated by Metro Vancouver and performed by BGC Engineering has developed IDF curves based on data from ten measurement sites. The curves are adjusted to the year 2050, and based on an extreme climate change scenario based on increased emission levels from now until then.

#### 2.4.3. Recommendations:

Based on the conservative climate scenario, monthly precipitation in Metro Vancouver will increase by 10-21% by the year 2050. Also, the frequency of extreme events will increase significantly, especially at lower durations. At most of the stations, what is now a 100-year storm will be a 50-year storm in 2050. As a result, any design features should be able to convey these higher peak flows while also being able to more effectively filter the metals and other roadside pollutants.

## 2.5. Stakeholder Engagement

Several stakeholders will be affected by the project during all phases; planning, construction, operation and decommissioning. The goal is to design the project such that stakeholder concerns are addressed. Data throughout the preliminary design stage was collected and incorporated into the detailed design and continued communication with the relevant parties has taken place throughout the progression of the design.

The stakeholder engagement strategy began with a stakeholder analysis. This process involved compiling a list of stakeholders, obtaining information on other unforeseen stakeholders, and researching the interested parties to determine their core values. In addition to the independent study done to understand the needs of project stakeholders, continuous communication with stakeholders



was made a priority. To date, stakeholder data has been collected through surveys to the general public, formal meetings with stakeholder officials/representatives, and through an open-house forum.

Inputs from stakeholders has been compiled and analyzed to inform the direction of the project. This input was be measured against current standards and regulations in order to provide project options. Since the majority of those providing feedback and suggestions are lay-people, stakeholder input was considered in relation to proven solutions within the scope of engineering. Not all initiatives will purely be design based. For example, changes in transportation and street-use behaviours, education on new signage and use of the new intersections is equally important to the effectiveness of the solutions provided.

Several lines of communication will remain open during and after project construction. The performance of the corridor and subsequent satisfaction of stakeholders will not be known until the Chancellor Boulevard is fully reopened and is being used during peak demand times. The recommendation is for BC Ministry of Transportation and Infrastructure (MOTI) to provide a feedback focused email account. This should remain under the responsibility of TranBC, the online face on MOTI. Major milestones of the project will continue to be communicated through a project website to ensure the public can readily access the information that pertaining to this redesign.



# 3. Detailed Design

# 3.1. Pedestrian Underpass

It was determined that an underpass would be the best suitable option for providing a safe passage across the Chancellor Boulevard corridor for pedestrians and cyclists crossing near the University Hill Elementary School. The tunnel will be constructed from cast-in-place reinforced concrete will have a width of 4.5 m and a clear height of 2.5m and consist of six elements: a suspended slab, two bearing/retaining walls, each supported by a strip footing, and a slab on grade. Design loads for the concrete elements were taken from CSA-S6-06, and their calculations can be found in Tables 2 and 3 of Appendix A. All concrete elements were designed to the CSA A23.3-14 standard. An MSE wall will stabilize the slope on the approach to the underpass.

The design of the retaining walls will have the capacity to sustain both flexural and axial loads. Flexural loads imposed on the wall include at-rest lateral earth pressures as well as worst-case lateral pressures based on traffic surcharges. Bearing capacity and axial loads were based on the assumption that tire area would be imposed directly onto the top of the wall. Strip footings were designed based on the soil bearing capacity, friction angle, and geotechnical reduction factor in the supplied geotechnical report. The slab on grade was designed for pedestrian loads therefore a 150mm thickness with temperature reinforcement was found to be sufficient. Required dimensions were calculated for the MSE wall section and an appropriate Nilex MSE wall system was chosen to suit. Design loads were the same as those used for the concrete tunnel elements. Tire loads are assumed to be imposed at a 3m distance from the edge of the wall.

### 3.2. Roadway

#### 3.2.1. Design Speed and Alignment

With the goal of reducing traffic speeds along the corridor, the design seeks to reclassify the road as an undivided arterial urban road, 2-lane UAU50, by the removal of the south 2 lanes. Horizontal circular curves that do not utilize super-elevation or reverse crown will be implemented in keeping with typical municipal urban design guidelines. The design will retain the existing alignment and cross-sections but will modify the intersection. Table 3-1 indicates the minimum design values.



Table 3-3-1: Minimum Design Values

| Design Feature                        | Parameter                         | Minimum Value |
|---------------------------------------|-----------------------------------|---------------|
| Horizontal Circular Curve             | Radius (no superelevation)        | 100m          |
| Horizontal Circular Curve with Spiral | Radius (4% superelevation)        | 80m           |
| Spiral Length                         | Ls                                | 22m           |
| Crest Curve                           | K Value (Stopping Sight Distance) | 7             |
| Sag Curve (no illumination)           | K Value (Stopping Sight Distance) | 13            |
| Sag Curve (illuminated road)          | K Value (Comfort Control)         | 6             |
| Laning                                | Width                             |               |

#### 3.2.2. Intersection Design

Campus Consulting conducted an intersection analysis to determine the best suited option given the design objectives of the project. Modelling for stop sign and signalized options was completed using Synchro 6 while Sidra Intersection 7.0 was used to better reflect roundabout conditions. Level of service, user safety, intersection delay, and cost were compared in a multi-point evaluation, with a roundabout being the preferred option. The roundabout was designed as per NCHRP 672 Roundabouts: An Informational Guide and BC Supplement to TAC Geometric Guidelines. The roundabout geometry is summarized in Table 3.2 and the detailed design can be found in the attached design drawings.

#### Table 3-2 Roundabout Geometry

| Design Feature                 | Value   |
|--------------------------------|---------|
| Inscribed Circle Diameter      | 40m     |
| Raised Central Island Diameter | 16m     |
| Circulatory Roadway Width      | 6m      |
| Entry Radius                   | 20-30m  |
| Exit Radius                    | 120m    |
| Fastest Path                   | 35km/hr |

#### 3.2.3. Pedestrian and Bike Improvements

Given the importance of increasing pedestrian and cyclist safety along the corridor, buffered bike lanes on the roadway, with a 1.5m wide bike lane and 0.6m buffer will be provided, designed to the NACTO Urban Bikeway Design Guide. For cyclists that do not feel comfortable on the roadway, the existing multi-use path will be widened to 3.0m and resurfaced to allow pedestrians and bicyclists to use the



path together. In addition, overhead pedestrian crossing lights will be added at major trailheads with Pacific Spirit Park so that pedestrians have safe crossing locations.

#### 3.2.4. Paint markings and signage

Additional road signs and markings will be implemented and will conform to BC Ministry of Transportation and Highways Manual of Standard Traffic Signs & Pavement Markings and City of Vancouver regulations on street signs and signals. Additionally, roundabout signage is designed to meet industry standard practice by satisfying signage requirements of the Transportation Association of Canada Manual of Uniform Control Devices for Canada.

### 3.3. Stormwater Management

Campus Consulting performed a hydraulic analysis of the Chancellor Boulevard using PCSWMM to determine a new stormwater management plan for the project area. A new stormwater system was designed to manage 100-year floods, taking into account projected increases in precipitation due to climate change. This system is comprised of two distinct source control sub-systems: a bioswale to collect runoff from the road, and a set of lawn basins to collect runoff from the area around the pedestrian underpass.

Roads will be sloped such that runoff from the road will flow into a bioswale designed to infiltrate 90% of annual precipitation and 90% of a 2-year 24-hour storm event. The design includes a 150 mm perforated underdrain and a trapezoidal drain rock reservoir. Weirs will be constructed along the length of the bioswale such that slopes will not exceed 2%. The underdrain will tie into the existing stormwater system to ensure that flooding is prevented when infiltration capacity is exceeded. The drain rock reservoir will also allow for some infiltration to help with groundwater recharge.

The rational method was used to determine runoff around the underpass, assuming an area of 1953 m3 and runoff coefficient C=0.375. A rainfall intensity value of 48 mm/h was obtained from local IDF curves assuming climate change scenarios. These values give a flow of 0.01 m3/s. Assuming a velocity of 1 m/s, a pipe diameter of 200 mm is required. Three lawn basins with 150 mm leads at a 1% slope will drain to this pipe at a 1% slope, ultimately tying into the main stormwater system.



# 4. Construction Management

# 4.1. Construction Specifications

All project construction will be subject to relevant municipal, provincial, and federal standards as follows:

- City of Vancouver Construction and Noise Bylaws
- University of British Columbia Construction and Noise Bylaws
- WorkSafeBC Workers Compensation Act, Occupational Health and Safety Regulations, and Employer and Employee Responsibilities
- CSA Standards for Occupational Health and Safety

All roadworks to conform to the following:

- City of Vancouver Street Design Guidelines and Construction Standards
- MMCD Design Guidelines (As Specified by CoV)
- BC Ministry of Transportation Standard Specifications for Highway Construction
- Transportation Association of Canada Manual of Uniform Control Devices for Canada

All structural concrete construction for pedestrian underpass is to abide by:

• CSA A23.3-14 Design of Concrete Structures 2014

In general, construction will adhere to the 2016 MOTI Standards for Highway Construction. Specific cases from this document are detailed in Appendix C.

## 4.2. Construction Sequencing

- 1) Site fencing installed
- 2) Clear/grub grass from median; windrow organic soils on median
- 3) Remove existing intersection



- 4) Install roundabout
  - a) Issues the intersection must be closed while the center island is being built or there must be a diversion
- 5) While the roundabout is under construction, remove the north lanes and existing drainage infrastructure
- 6) Mill and grind the asphalt for recycling from the north lanes
- 7) Excavate down to finished grade on north lanes
- 8) Stockpile material from north lanes adjacent to fill area around the pedestrian underpass
- 9) Prepare base and pave the north lanes
- 10) Mill and grind the asphalt for recycling from the south lanes
- 11) Stockpile material
- 12) Excavate down to finished grade on south lanes, in bioswale region,
- 13) At this point in the construction, two features will be built concurrently: the bioswale and the pedestrian underpass
- 14) Pedestrian Underpass:
  - a) Build temporary diversion road around pedestrian underpass
  - b) Construct Cast-In-Place Footings
    - i) Excavate to foundation base and compact
    - ii) Assemble formwork for strip footings
    - iii) Assemble and place reinforcement cages
    - iv) Pour concrete footings
  - c) Construct Cast-In-Place Walls
  - d) Construct Cast-In-Place Slab on Grade
  - e) Construct Cast In Place Slab (upper)
  - f) Backfill and build MSE wall around cast-in-place tunnel
  - g) Pave road over pedestrian underpass
  - h) Dismantle temporary road
  - i) Construct drainage system for underpass
- 15) Bioswale:
  - a) Excavate trench
  - b) Install drain rock reservoir and drain pipe



- c) Tie into existing drainage system
- d) Install topsoil
- e) Sod and landscaping/gardening
- f) Install weirs
- 16) Install multi-use path
- 17) Landscaping and hydroseeding along sides of roads



Figure 4-1 Schematic Construction Schedule

Please see Detailed Construction Schedule in Appendix D.

### 4.3. Anticipated Issues

- Traffic management will be an ongoing concern, more acute at some points in construction. Traffic will be most impacted during the construction of the pedestrian underpass, when it will be rerouted around the fill area on one lane and controlled by flaggers.
  - a) Solution: Traffic impacts may be mitigated if the construction schedule is shifted such that the pedestrian underpass is constructed during the summer, while classes are not in session.
- 2) While the road is being constructed near University Hill Elementary School the existing pedestrian crossing will be gone.
  - a) A temporary crossing will need to be provided for local pedestrians and students attending University Hill Elementary School. Coordination between construction flaggers and school staff should take place in order to ensure that the needs of the elementary school students and staff are met.
- 3) High Rainstorm event, delaying excavations and causing erosion of earth works



- a) Ensure earthworks and fill are compacted to acceptable standards to maintain soil integrity, avoid heavy machinery on compacted soils during rain events and provide adequate stormwater management on site to mitigated ponding
- 4) Jaywalking through the construction site
  - Fencing will be installed around active construction areas to ensure that people do not cross into construction areas. Outside of the construction areas, existing crossings will be left in place until improvements are built
- 5) There will be many different kinds of material being excavated that should not be mixed together
  - a) Separate stockpiles will be maintained for milled asphalt, organic soil, and inorganic fill
- 6) The roundabout will not be usable with the island is being constructed. The road will have to be closed at this point
  - a) Signs should be put at each end of the corridor warning road users that a detour to 10th ave is necessary for access to the university
- 7) The bioswale, especially the topsoil portion, will be extraordinarily vulnerable to sediments transported by water. Water is directed to the bioswales by gravity. When functioning under ordinary circumstances, water percolates down through the pores in the topsoil and infiltrates below. When the water is carrying high loads of sediment, a condition that occurs to a great extent during construction, the sediment will clog the pore spaces and reduce the hydraulic conductivity of the soil, making infiltration slower. This will greatly reduce the effectiveness of the bioswale
  - a) Very careful erosion and sediment measures should be taken during construction to prevent excessive sediment from entering the bioswale. Just as in any construction site, sediment barriers should be placed at entrances to the bioswale to filter incoming runoff.

### 4.4. Construction Cost

The total anticipated cost for the project is \$3.85 Million. Please see Appendix E for a detailed cost breakdown.



# 5. Operations and Maintenance

The operations and maintenance required for the corridor has been divided into two main categories, "Minor" and "Major", respectively. Minor O & M includes all tasks that maintain the current operation and design of the main roadway and other aspects of the corridor and are required on an annual or near-annual basis while Major O &M tasks are those which require significant reconstruction of the corridor.

As UBC's future needs for the Chancellor Boulevard Corridor may change, we have chosen to forecast operations and maintenance for a 20-year period as this is approximately when major repairs will need to be made, thus affording an opportunity to address new demands and industry practice into the corridor at such time. Additionally, Campus Consulting cannot reasonably attempt to forecast operations and maintenance costs beyond such time line.

We anticipate the corridor to have a useful life far greater than 20 years and believe that the design will meet the needs of our client well into the future. The corridor can be expected to function indefinitely so long as UBC and the City of Vancouver feel that the cost-benefit analysis of its use is returning satisfactory results.

## 5.1. Minor Operations and Maintenance

As with most large infrastructure projects, more significant repairs such as minor road surface repair will tend to increase in frequency as the corridor ages. We acknowledged that these items may occur several times over our initial lifespan projection of 20 years, however, to simplify our estimates we have considered them to occur on a linear basis and amortized these costs into average annual costs so that they may be added to the other operational costs to create a total average annual cost per year.



#### The following table below outlines all tasks we believed to be of "Minor" status:

Table 5-1 Minor Operations and Maintenance Line Items

| Item   | Applies to | Work Done By      | Occurrence                           |
|--|------------|-------------------|--------------------------------------|
| Tree and Brush Pruning and Removal           | Corridor   | Metro Van (Parks) | Annual                               |
| Trash/Litter Removal                         | Bioswale   | Metro Van (Parks) | Quarterly                            |
| Landscaping                                  | Bioswale   | Metro Van (Parks  | Annual                               |
| Seasonal Check and Cleaning of<br>Road Signs | Corridor   | Metro Van (Parks) | Annual                               |
| Reseeding and Fertilizing                    | Corridor   | Metro Van (Parks  | Annual                               |
| Centerline Re-Painting                       | Road       | MoT (Contractor)  | Every 2 Years                        |
| All Other Lines                              | Road       | MoT (Contractor)  | Every 5 Years                        |
| Crack Sealing                                | Road       | MoT (Contractor)  | 5 Times in 20 Years                  |
| Patching                                     | Road       | MoT (Contractor)  | 5 Times in 20 Years                  |
| Pothole Filling                              | Road       | MoT (Contractor)  | 3 Times in 20 Years                  |
| Structural Inspection                        | Underpass  | MoT (Contractor)  | Annual                               |
| Lighting Replacement and<br>Maintenance      | Underpass  | MoT (Contractor)  | Every 5 Years                        |
| Road De-Icing & Snow Plowing                 | Road       | CoV               | 6 Months of Year                     |
| Delineator Replacement                       | Road       | CoV               | Bi-Annual                            |
| Mowing                                       | Corridor   | Metro Van (Parks  | Seasonally &<br>Monthly in<br>Summer |
| Weed Control                                 | Corridor   | Metro Van (Parks  | Seasonally &<br>Monthly in<br>Summer |
| Culvert (x2) Inspection and Cleaning         | Drainage   | MoT (Contractor)  | Annual                               |
| Storm Sewer Inspection and<br>Cleaning       | Drainage   | MoT (Contractor)  | Every 5 Years                        |
| Mutli-Use Path Repairs                       | Corridor   | CoV               | Every 5 Years                        |

We estimate Minor O&M to be account for a total average annual cost of \$161,500 2018 Canadian Dollars. Using a nominal inflation rate of 3%, we have forecasted these costs for the first 20 years of the corridors service in the table below.

Table 5-2 Minor Operations and Maintenance Costs

|               | 2020      | 2024      | 2029      | 2034      | 2039      |
|---------------|-----------|-----------|-----------|-----------|-----------|
| Service Year: | 1         | 5         | 10        | 15        | 20        |
| Cost:         | \$171,335 | \$192,839 | \$223,554 | \$259,160 | \$300,438 |



# 5.2. Major Operations and Maintenance

Major Operations and Maintenance are summarized as the larger construction repair and redesign work required on a non-frequent occurrence as compared to tasks associated with Minor O&M. Campus consulting has identified the tasks deemed to be Major in the following table.

Table 5-3 Major Operations and Maintenance Line Items

| Item                           | Applies to      | Work Done By     | Occurrence     |
|--------------------------------|-----------------|------------------|----------------|
| Road Resurfacing and Reshaping | Road            | MoT (Contractor) | Every 20 Years |
| Curb and Gutter Repair         | Road & Drainage | MoT (Contractor) | Every 20 Years |

We have estimated the total cost for Major O&M to be \$1,000,000 2018 Canadian Dollars. Using a nominal inflation rate of 3% we have forecasted the first projected occurrence of Major O&M to have cost of \$1,860,295 in 2039 Canadian Dollars.



# 6. Conclusion

Campus Consulting was retained to complete a detailed redesign of the Chancellor Boulevard corridor. The objectives governing the redesign process include:

- meeting all future transportation demands,
- prioritizing buses, cyclists, and pedestrians and ensuring the safety of all road users,
- avoiding negatively impacting Pacific Spirit Park and the habitats it provides,
- accommodating and improving drainage, and
- minimizing costs and optimizing the construction schedule.

Pursuant to these goals, the Campus Consulting project team has created a detailed design including features such as a pedestrian underpass and vehicle roundabout at the Hamber Road intersection, marked pedestrian crosswalks with beacons at all pedestrian crossings, a multi-use path made of permeable pavement, narrowed vehicle travel lanes, and dedicated bicycle lanes.

The design is unique it that it will include a large infiltration swale, reducing the quantity and improving the quality of road runoff; it has a separated multi-use path, allowing pedestrians some measure of segregation from motorized vehicles; it removes the median between vehicle travel lanes, slowing traffic; and construction sequencing has been planned to be the least disruptive to the surrounding neighborhood as the road can be built independently of the infiltration swale, minimizing the constriction of traffic. Stakeholders have been involved throughout the entire design process and will continue to be involved in this landmark project as it proceeds.



# 7. Software & References

### 7.1. Software

#### 7.1.1. Civil3D

Civil3D is a civil engineering modelling and drafting program produced by Autodesk. It was used to produce the design drawings as well as determine quantities for the construction pricing and schedule.

#### 7.1.2. PCSWMM

Stormwater modeling on this project was performed with PCSWMM. This program allowed us to accurately delineate Chancellor Boulevard as a set of catchments, and also to model outfalls for each catchment. Also, the program allowed us to input historical long-term precipitation data as well as create a design storm in order to test short and long-term outflow. Further to this, PCSWMM allows the user to model sites with Low Impact Development features. In the case of this project, it allowed us to model the site with and without infiltration swales in order to verify that the infiltration swale design created using Metro Vancouver's Stormwater Source Control Guideline performs as expected.

#### 7.1.3. ETCulvert

The culvert segments were designed in software using "ETCulvert" which was created by Eriksson Software located in Tampa, Florida. The program allows for fully automatic design and analysis of both 3-sided and 4-sided culverts. It incorporates design standards from AASHTO and LRFD/LRFR specifications. The program is flexible in design allowing for input of many design parameter inputs and updates the design as parameters are changed. It is a fast-efficient program that provides a comprehensive rebar or WWF (mesh) schedule and rebar layout which can be printed and used as drawing to construct the culvert segments. Also, the program is capable of producing renderings of your design, which gives a visual representation of the rebar cage within the concrete structure.

#### 7.1.4. Synchro 6 plus SimTraffic

Synchro is a traffic planning and analysis software produced by Trafficware which is capable of modelling and analyzing street networks. Input data in the form of traffic volume, traffic content, and



peak hour factors are required to be determined prior to modelling using Synchro. Campus Consulting used Synchro to analyze potential intersection options for Chancellor Boulevard and Hamber Road.

#### 7.1.5. Sidra Intersection 7.0

Similar to Synchro, Sidra is a traffic analysis software that models traffic networks based and is developed by Sidra Solutions. Upon acquiring base input data, users may specify intersection details and determine service outputs. Campus Consulting used Sidra specifically for modelling a roundabout at the intersection of Chancellor Boulevard and Hamber Road as it is considered by industry to provides better results and accuracy than Synchro for these types of intersection.



### 7.2. References

- [1] City of Vancouver, "Transportation 2040 Plan for the City of Vancouver," 31 October 2012. [Online]. Available: http://www.vancouver.ca/files/cov/transportation-2040-plan.pdf.
- [2] UBC Campus and Community Planning, "UBC-Transportation-Plan-2014\_Oct.pdf," October 2014.
   [Online]. Available: https://planning.ubc.ca/sites/planning.ubc.ca/files/documents/transportation/plans/UBC-Transportation-Plan-2014\_Oct.pdf.
- [3] National Association of City Transportation Officials, "Speed Reduction Mechanisms," [Online]. Available: https://nacto.org/publication/urban-street-design-guide/design-controls/designspeed/speed-reduction-mechanisms/. [Accessed 20 November 2017].
- [4] Binnie Civil Engineering Consultants, "Block F Development Stormwater Management Plan," October 2015. [Online]. Available: http://www.universityendowmentlands.gov.bc.ca/library/Block%20F%20Update/12-125%20Stormwater%20Management%20Report%20(2015.10.30).pdf. [Accessed 8 November 2017].
- [5] BGC Engineering Ltd., "Climate Change (2050) Adjusted IDF Curves: Metro Vancouver Climate Stations," Metro Vancouver, 6 May 2009. [Online]. Available: http://www.metrovancouver.org/services/liquidwaste/LiquidWastePublications/ClimateChange2050AdjustedIDFCurves2009.pdf. [Accessed 8 November 2017].
- [6] AECOM, "Hydrogeologic Stormwater Management Strategy Phase 1 Desktop Assessment," University of British Columbia Campus and Community Planning, February 2013. [Online]. Available: https://planning.ubc.ca/sites/planning.ubc.ca/files/documents/projectsconsultations/consultations/Hydrogeologic%20Stormwater%20Management%20Strategy%20-%20phase%201.pdf. [Accessed 17 October 2017].
- [7] Piteau Associates Geotechnical and Hydrogeological Associates, "Hydrogeological and Geotechnical Assessment of Northwest Area UBC Campus, Vancouver," September 2002. [Online]. Available: https://connect.ubc.ca/bbcswebdav/pid-4397280-dt-content-rid-22676722\_1/courses/SIS.UBC.CIVL.445.101.2017W1.87577/HydroGeoStudy-ubc-piteau-2002%281%29.pdf. [Accessed 10 October 2017].



- [8] City of Victoria, "Johnson Street Bridge Risk Register," 2010, June. [Online]. Available: http://www.johnsonstreetbridge.com/wp-content/uploads/2010/06/Appendix-O.pdf. [Accessed 24 November 2010].
- [9] Pottinger Gaherty Environmental Consultants Ltd., "Musqueam Block F Environmental Impact Assessment," Musqueam Indian Band, August 2014. [Online]. Available: http://www.universityendowmentlands.gov.bc.ca/library/Block\_F\_App\_A\_OverviewEnvironmental ImpactAssessment.pdf. [Accessed 19 November 2017].
- [10 Spanish Bank Streamkeepers, "Spanish Banks Creek in Vancouver, British Columbia (B.C.)," Spanish
   Bank Streamkeepers, 10 March 2006. [Online]. Available: http://www.urbanstreams.org/creek\_spanishbanks.html. [Accessed 25 October 2017].
- [11 Environment Canada, "Species at Risk in Our Backyard," Environment Canada, [Online]. Available:http://www.env.gov.bc.ca/lower
  - mainland/electronic\_documents/19795%20Species%20at%20Risk%20Booklet%20insides%20web.p df. [Accessed 13 October 2017].
- [12 AECOM, "University Endowment Lands Integrated Stormwater Management Plan Draft," AECOM,] September 2017. [Online]. Available: http://uelcommunity.com/wp-

content/uploads/2017/09/RPT-2017-09-12-UEL-ISMP-60222155-Final-DRAFT-Main-Document.pdf. [Accessed 30 October 2017].

- [13 U.S. Department of Transportation Federal Highway Administration, "Wildlife Crossing Structure
   Handbook Design and Evaluation in North America," Central Federal Lands Highway Division, March 2011. [Online]. Available: https://roadecology.ucdavis.edu/files/content/projects/DOT-
  - FHWA\_Wildlife\_Crossing\_Structures\_Handbook.pdf. [Accessed 1 November 2017].
- [14 D. J. E. Armstrong, "Vancouver Geology," 1990. [Online]. Available: http://www.gac-cs.ca/publications/VancouverGeology.pdf. [Accessed 28 October 2017].
- [15 British Columbia Conservation Data Centre, "BC Species & Ecosystems Explorer," British Columbia

Ministry of Environment, [Online]. Available: https://www2.gov.bc.ca/gov/content/environment/plants-animals-ecosystems/conservation-datacentre/explore-cdc-data/species-and-ecosystems-explorer. [Accessed 5 November 2017].



# Appendix A: Species List

| English<br>Name   | Global<br>Status | Prov<br>Status | COSEWIC                     | BC<br>List | SARA                            | General<br>Status<br>Canada                  | Name                              | Class<br>(English)       | Kingdom  | Regional Dist  |
|---|------------------|----------------|-----------------------------|------------|---------------------------------|--|-----------------------------------|--------------------------|----------|--|
| Name  | Status           | Status         | COSEVVIC                    | LISU       | SAKA                            | Canada                                       | Category                          | (English)                | Kingdom  | MVRD;CRD;CVRD;RDN;ACRD;CX  |
| Great Blue<br>Heron, Fannini<br>Subspecies<br>Vancouver | G5T4             | S2S3B,S4<br>N  | SC (Mar<br>2008)            | Blue       | 1-SC (Feb<br>2010)              |  | Vertebrate Animal                 | birds                    | Animalia | RD;STRD;CVRD;SCRD;SLRD;CX<br>RD;STRD;PWRD;SCRD;SLRD;CBR<br>D;MWRD;CCRD;SQCRD;KSRD;FV<br>RD                     |
| Island<br>Beggarticks                                   | G3               | S3             | SC (Nov<br>2001)            | Blue       | 1-SC (Jun<br>2003)              | 3 - Sensitive<br>(2010)                      | Vascular Plant                    | dicots                   | Plantae  | MVRD;CRD;CVRD;RDN;ACRD;CX<br>RD;STRD;SLRD;CCRD;FVRD<br>MVRD;CRD;CVRD;RDN;ACRD;CX                               |
| Marbled<br>Murrelet<br>Western<br>Screech-owl,          | G3               | S3B,S3N        | T (May 2012)                | Blue       | 1-T (Jun<br>2003)               | 1 - At Risk<br>(2005)                        | Vertebrate Animal                 | birds                    | Animalia | RD;STRD;PWRD;SCRD;SLRD;MW<br>RD;CCRD;SQCRD;KSRD;FVRD<br>MVRD;CRD;CVRD;RDN;ACRD;CX<br>RD;STRD;PWRD;SCRD;SLRD;MW |
| Kennicottii<br>Subspecies                               | G5T4             | S2S3           | T (May 2012)                | Blue       | 1-SC (Jan<br>2005)              |  | Vertebrate Animal                 | birds                    | Animalia | RD;CCRD;SQCRD;KSRD;SKRD;FV<br>RD<br>MVRD;CRD;CVRD;RDN;ACRD;CX<br>RD;STRD;PWRD;SCRD;SLRD;TNR                    |
| Band-tailed   |                  |                | SC (Nov                     |            | 1-SC (Feb                       | 3 - Sensitive                                |                                   |                          |          | D;MWRD;CCRD;SQCRD;KSRD;FV  |
| Pigeon  | G4               | S3S4B          | 2008)                       | Blue       | 2011)                           | (2005)                                       | Vertebrate Animal                 | birds                    | Animalia | RD   |
| Northern Red-<br>legged Frog                            | G4               | S3             | SC (May<br>2015)            | Blue       | 1-SC (Jan<br>2005)              | 3 - Sensitive<br>(2005)                      | Vertebrate Animal                 | amphib                   | Animalia | MVRD;CRD;CVRD;RDN;ACRD;CX<br>RD;STRD;PWRD;SCRD;SLRD;MW<br>RD;CCRD;SQCRD;FVRD                                   |
| Twisted Oak   | 04               | 55             | SC (Nov                     | Diac       | 1-SC (Jul                       | (2003)                                       | Vertebrate Amma                   | umphilo                  | Annana   | hb,cenb,seenb,r vhb  |
| Moss  | GNR              | S3             | 2014)                       | Blue       | 2005)                           |  | Nonvasc. Plant                    |                          | Plantae  | MVRD;CRD;CVRD;RDN  |
| Green Sturgeon<br>Western Pond                          | G3               | S1N            | SC (Nov<br>2013)<br>XT (May | Red        | 1-SC (Aug<br>2006)<br>1-XX (Jan | 2 - May be at<br>risk (2005)<br>.2 - Extinct | Vertebrate Animal                 | ray-finned<br>fishes     | Animalia | MVRD;SLRD;SQCRD;KSRD;SKRD  |
| Turtle<br>Oregon  | G3G4             | SX             | 2012)                       | Red        | 2005)                           | (2005)                                       | Vertebrate Animal<br>Invertebrate | turtles                  | Animalia | MVRD;FVRD  |
| Forestsnail   | G3G4             | S2             | E (Apr 2013)                | Red        | 1-E (Jan 2005)                  | 1 - At Risk                                  | Animal                            | gastropods<br>ray-finned | Animalia | MVRD;FVRD  |
| Salish Sucker<br>Painted Turtle -                       | G1               | S1             | T (Nov 2012)                | Red        | 1-E (Jan 2005)                  | (2000)                                       | Vertebrate Animal                 | fishes                   | Animalia | MVRD;FVRD  |
| Pacific Coast<br>Population<br>Puget                    | G5T2             | S2             | T (Nov 2016)                | Red        | 1-E (Dec<br>2007)<br>1-XX (Jan  |  | Vertebrate Animal<br>Invertebrate | turtles                  | Animalia | MVRD;CRD;CVRD;RDN;ACRD;CX<br>RD;STRD;PWRD;SCRD;FVRD  |
| Oregonian   | G3               | SX             | XT (Apr 2013)               | Red        | 2005)                           |  | Animal                            | gastropods               | Animalia | MVRD;CRD;FVRD  |



|                |      |     |              |        |                | 6 - Not       |                   |            |          | MVRD;CRD;CVRD;RDN;ACRD;CX    |
|----------------|------|-----|--------------|--------|----------------|---------------|-------------------|------------|----------|------------------------------|
|                |      |     |              |        | 1-T (Jun       | Assessed      | Invertebrate      |            |          | RD;STRD;PWRD;SLRD;TNRD;FVR   |
| Dun Skipper    | G5   | S2  | T (Apr 2013) | Red    | 2003)          | (2000)        | Animal            | insects    | Animalia | D                            |
|                |      |     |              |        |                |               |                   |            |          | MVRD;CRD;CVRD;RDN;ACRD;CX    |
| Northern       |      |     |              |        |                |               | Invertebrate      |            |          | RD;STRD;PWRD;SCRD;MWRD;C     |
| Abalone        | G3G4 | S2  | E (Apr 2009) | Red    | 1-E            |               | Animal            | gastropods | Animalia | CRD;SQCRD;KSRD;SKRD          |
| Streambank     |      |     |              |        |                | 1 - At Risk   |                   |            |          |                              |
| Lupine         | G2G4 | S1  | E (Nov 2002) | Red    | 1-E (Jan 2005) | (2010)        | Vascular Plant    | dicots     | Plantae  | MVRD;CRD                     |
| Greenish Blue, |      |     |              |        |                |               |                   |            |          |                              |
| Insulanus      |      |     |              |        | 1-E (Jun       |               | Invertebrate      |            |          |                              |
| Subspecies     | G5TH | SH  | E (May 2012) | Red    | 2003)          |               | Animal            | insects    | Animalia | MVRD;CRD;CVRD;RDN;CXRD       |
| Oregon Spotted |      |     |              |        | 1-E (Jun       | 1 - At Risk   |                   |            |          |                              |
| Frog           | G2   | S1  | E (May 2011) | Red    | 2003)          | (2005)        | Vertebrate Animal | amphibians | Animalia | MVRD;FVRD                    |
|                |      |     |              |        | 1-E (Jun       | 1 - At Risk   |                   | ray-finned |          |                              |
| Nooksack Dace  | G3   | S1  | E (Apr 2007) | Red    | 2003)          | (2000)        | Vertebrate Animal | fishes     | Animalia | MVRD;FVRD                    |
| Pacific Water  |      |     |              |        | 1-E (Jun       | 1 - At Risk   |                   |            |          |                              |
| Shrew          | G4   | S2? | E (Apr 2016) | Red    | 2003)          | (2005)        | Vertebrate Animal | mammals    | Animalia | MVRD;SLRD;FVRD               |
|                |      |     | - 4          |        | 1-E (Jun       | 1 - At Risk   |                   |            |          |                              |
| Spotted Owl    | G3G4 | S1  | E (Mar 2008) | Red    | 2003)          | (2005)        | Vertebrate Animal | birds      | Animalia | MVRD;SLRD;TNRD;OSRD;FVRD     |
|                |      |     | - (          |        | 1-SC (Jun      | 3 - Sensitive |                   |            |          | MVRD;CRD;CVRD;RDN;CXRD;ST    |
| Barn Owl       | G5   | S2? | T (Nov 2010) | Red    | 2003)          | (2005)        | Vertebrate Animal | birds      | Animalia | RD;NORD;CSRD;OSRD;FVRD       |
| Mountain       |      |     | SC (May      |        | 1-SC (Jun      | 4 - Secure    |                   |            |          |                              |
| Beaver         | G5   | S4  | 2012)        | Yellow | 2003)          | (2005)        | Vertebrate Animal | mammals    | Animalia | MVRD;TNRD;OSRD;FVRD          |
|                |      |     |              |        |                |               |                   |            |          | MVRD;STRD;PWRD;SCRD;SLRD;    |
| Coastal Tailed | ~    | 6.4 | SC (Nov      | M. II. | 1-SC (Jun      | 3 - Sensitive |                   |            | <b>A</b> | TNRD; MWRD; CCRD; SQCRD; KSR |
| Frog           | G4   | S4  | 2011)        | Yellow | 2003)          | (2005)        | Vertebrate Animal | amphibians | Animalia | D;OSRD;FVRD                  |



# Appendix B: Underpass Sample Calculations

#### Table B-1 – Constants and Assumptions for Underpass Loading, Structural Design

|                | f <sub>c</sub> '= | 30   | Мра   |
|----------------|-------------------|------|-------|
|                | I <sub>C</sub> –  | 30   | ινιμα |
|                | f <sub>y</sub> =  | 400  | MPa   |
|                | height =          | 2.5  | m     |
|                | span =            | 4.5  | m     |
|                | ф <sub>с</sub> =  | 0.65 |       |
|                | φ <sub>s</sub> =  | 0.85 |       |
| Truck Tire     | w =               | 0.6  | m     |
| Truck The      | =                 | 0.25 | m     |
| Unfactored     | P =               | 87.5 | kN    |
|                | s =               | 1.8  | m     |
|                | α1 =              | 0.8  |       |
| Assume pin-pin | k =               | 1    |       |



#### Table B-2 – Axial Loads on Concrete Retaining Wall

|            | D     | Е | Р | L*    | К | W | V | S    | EQ | F | А | Н |
|------------|-------|---|---|-------|---|---|---|------|----|---|---|---|
| LOADS (kN) | 23.12 | 0 | 0 | 97.22 | 0 | 0 | 0 | 4.95 | 0  | 0 | 0 | 0 |

|                              |       |       |        |       |      |        |        |       |      |      |        | 1     |      |        |
|------------------------------|-------|-------|--------|-------|------|--------|--------|-------|------|------|--------|-------|------|--------|
|                              |       | PERMA | NENT L | .OADS | -    | TRANSI | TORY L | .OADS |      | EXC  | EPTION | AL LO | ADS  |        |
|                              | Loads | D     | Е      | Р     | L*   | К      | W      | V     | S    | EQ   | F      | А     | Н    | TOTAL  |
| Fatigue Limit State          | FLS1  | 1.00  | 1.00   | 1.00  | 1.00 | 0.00   | 0.00   | 0.00  | 0.00 | 0.00 | 0.00   | 0.00  | 0.00 | 120.34 |
| Convises hility Limit States | SLS1  | 1.00  | 1.00   | 1.00  | 0.90 | 0.80   | 0.00   | 0.00  | 1.00 | 0.00 | 0.00   | 0.00  | 0.00 | 115.57 |
| Serviceability Limit States  | SLS2  | 0.00  | 0.00   | 0.00  | 0.90 | 0.00   | 0.00   | 0.00  | 0.00 | 0.00 | 0.00   | 0.00  | 0.00 | 87.50  |
|                              | ULS1  | 1.20  | 1.25   | 1.05  | 1.70 | 0.00   | 0.00   | 0.00  | 0.00 | 0.00 | 0.00   | 0.00  | 0.00 | 193.02 |
|                              | ULS2  | 1.20  | 1.25   | 1.05  | 1.60 | 1.15   | 0.00   | 0.00  | 0.00 | 0.00 | 0.00   | 0.00  | 0.00 | 183.30 |
|                              | ULS3  | 1.20  | 1.25   | 1.05  | 1.40 | 1.00   | 0.50   | 0.50  | 0.00 | 0.00 | 0.00   | 0.00  | 0.00 | 163.85 |
|                              | ULS4  | 1.20  | 1.25   | 1.05  | 0.00 | 1.25   | 1.65   | 0.00  | 0.00 | 0.00 | 0.00   | 0.00  | 0.00 | 27.74  |
| Ultimate Limit States        | ULS5  | 1.25  | 1.25   | 1.05  | 0.00 | 0.00   | 0.00   | 0.00  | 0.00 | 1.00 | 0.00   | 0.00  | 0.00 | 28.90  |
|                              | ULS6  | 1.20  | 1.25   | 1.05  | 0.00 | 0.00   | 0.00   | 0.00  | 0.00 | 0.00 | 1.30   | 0.00  | 0.00 | 27.74  |
| T                            | ULS7  | 1.20  | 1.25   | 1.05  | 0.00 | 0.00   | 0.90   | 0.00  | 0.00 | 0.00 | 0.00   | 1.30  | 0.00 | 27.74  |
|                              | ULS8  | 1.20  | 1.25   | 1.05  | 0.00 | 0.00   | 0.00   | 0.00  | 0.00 | 0.00 | 0.00   | 0.00  | 1.00 | 27.74  |
|                              | ULS9  | 1.35  | 1.25   | 1.05  | 0.00 | 0.00   | 0.00   | 0.00  | 0.00 | 0.00 | 0.00   | 0.00  | 0.00 | 31.21  |

#### Per Table 3.1, CSA S6-06



#### Table B-3 – Lateral earth loads on the retaining wall

|            | D | E      | Р | L*    | К | W | V | S | EQ | F | Α | Н |
|------------|---|--------|---|-------|---|---|---|---|----|---|---|---|
| LOADS (kN) | 0 | 11.875 | 0 | 15.20 | 0 | 0 | 0 | 0 | 0  | 0 | 0 | 0 |

|                              |       | PERM | IANENT L | OADS | -    | TRANSI | TORY L | .OADS |      | EXC  | EPTION | NAL LO | ADS  |       |
|------------------------------|-------|------|----------|------|------|--------|--------|-------|------|------|--------|--------|------|-------|
|                              | Loads | D    | E        | Р    | L*   | К      | W      | V     | S    | EQ   | F      | А      | Н    | TOTAL |
| Fatigue Limit State          | FLS1  | 1.00 | 1.00     | 1.00 | 1.00 | 0.00   | 0.00   | 0.00  | 0.00 | 0.00 | 0.00   | 0.00   | 0.00 | 27.08 |
| Conviscophility Limit States | SLS1  | 1.00 | 1.00     | 1.00 | 0.90 | 0.80   | 0.00   | 0.00  | 1.00 | 0.00 | 0.00   | 0.00   | 0.00 | 25.56 |
| Serviceability Limit States  | SLS2  | 0.00 | 0.00     | 0.00 | 0.90 | 0.00   | 0.00   | 0.00  | 0.00 | 0.00 | 0.00   | 0.00   | 0.00 | 13.68 |
|                              | ULS1  | 1.20 | 1.25     | 1.05 | 1.70 | 0.00   | 0.00   | 0.00  | 0.00 | 0.00 | 0.00   | 0.00   | 0.00 | 40.68 |
|                              | ULS2  | 1.20 | 1.25     | 1.05 | 1.60 | 1.15   | 0.00   | 0.00  | 0.00 | 0.00 | 0.00   | 0.00   | 0.00 | 39.16 |
|                              | ULS3  | 1.20 | 1.25     | 1.05 | 1.40 | 1.00   | 0.50   | 0.50  | 0.00 | 0.00 | 0.00   | 0.00   | 0.00 | 36.12 |
|                              | ULS4  | 1.20 | 1.25     | 1.05 | 0.00 | 1.25   | 1.65   | 0.00  | 0.00 | 0.00 | 0.00   | 0.00   | 0.00 | 14.84 |
| Ultimate Limit States        | ULS5  | 1.25 | 1.25     | 1.05 | 0.00 | 0.00   | 0.00   | 0.00  | 0.00 | 1.00 | 0.00   | 0.00   | 0.00 | 14.84 |
|                              | ULS6  | 1.20 | 1.25     | 1.05 | 0.00 | 0.00   | 0.00   | 0.00  | 0.00 | 0.00 | 1.30   | 0.00   | 0.00 | 14.84 |
|                              | ULS7  | 1.20 | 1.25     | 1.05 | 0.00 | 0.00   | 0.90   | 0.00  | 0.00 | 0.00 | 0.00   | 1.30   | 0.00 | 14.84 |
|                              | ULS8  | 1.20 | 1.25     | 1.05 | 0.00 | 0.00   | 0.00   | 0.00  | 0.00 | 0.00 | 0.00   | 0.00   | 1.00 | 14.84 |
|                              | ULS9  | 1.35 | 1.25     | 1.05 | 0.00 | 0.00   | 0.00   | 0.00  | 0.00 | 0.00 | 0.00   | 0.00   | 0.00 | 14.84 |

#### Per Table 3.1, CSA S6-06



| Bearing<br>Calculati                                    | Wall Axial Load<br>ions   |   |                                       |  |   |
|---|---|---|---------------------------------------|--|---|
| 1. Min T  | hickness  | t =   | 0.12                                  | m  |   |
| 2. Bearir<br>Strength                                   |   | Br =  | 1193.4                                | kN                                       | Greater than a tire load and<br>dead load |
| 3. Factor   | red Axial Load Resistance   | <b>I</b> <sub>b</sub> <   | 2.76                                  | m  | < 1.8 m                                   |
|   |   | I <sub>b</sub> =  | 1                                     | m  | (assume UDL)                              |
|   |   | A <sub>g</sub> =  | 0.12                                  | m²                                       |   |
|   |   | P <sub>r</sub> =  | 486.28                                | kN/m                                     | Resistance greater than load              |
|   |   | P <sub>f</sub> =  | 193.02                                | kN/m                                     | -   |
| 4. Deter  | mine min reinf.   | A <sub>g</sub> =  | 12000<br>0                            | mm²                                      |   |
| Horizon   | tal reinf.  | A <sub>h,min</sub> =  | 240                                   | mm²/m                                    |   |
|   |   |   |                                       |  |   |
| d <sub>b</sub> =<br>A <sub>b</sub> =                    | Assume 15M rebar<br>15 mm<br>200 mm <sup>2</sup>  | s =<br>s = ?  | 833.33<br>33<br>=                     | mm<br>0 36                               | m   |
| d <sub>b</sub> =<br>A <sub>b</sub> =                    |   | s =<br>s, <sub>max</sub> = ?  |                                       | mm<br>0.36<br>0.5                        | m<br>m                                    |
|   | 15 mm   |   | 33                                    | 0.36                                     |   |
|   | 15 mm<br>200 mm <sup>2</sup>  | s, <sub>max</sub> = ?   | 33<br>=<br>0.36                       | 0.36<br>0.5                              |   |
|   | 15 mm<br>200 mm <sup>2</sup><br>HORIZONTAL SPACING  | s <sub>,max</sub> = ?<br>s <sub>,max</sub> =  | 33<br>=<br>0.36                       | 0.36<br>0.5<br>m                         |   |
| A <sub>b</sub> =  | 15 mm<br>200 mm <sup>2</sup><br>HORIZONTAL SPACING  | s <sub>,max</sub> = ?<br>s <sub>,max</sub> =<br>A <sub>h</sub> =                                | 33<br>=<br>0.36<br>556                | 0.36<br>0.5<br>m<br>mm²/m                |   |
| A <sub>b</sub> =<br>Vertical                            | 15 mm<br>200 mm <sup>2</sup><br>HORIZONTAL SPACING<br>reinf.<br>Assume 15M rebar          | S <sub>,max</sub> = ?<br>S <sub>,max</sub> =<br>A <sub>h</sub> =<br>A <sub>v,min</sub> =        | 33<br>=<br>0.36<br>556<br>180         | 0.36<br>0.5<br>m<br>mm²/m<br>mm²/m<br>mm |   |
| A <sub>b</sub> =<br><b>Vertical</b><br>d <sub>b</sub> = | 15 mm<br>200 mm <sup>2</sup><br>HORIZONTAL SPACING<br>reinf.<br>Assume 15M rebar<br>15 mm | s, <sub>max</sub> = ?<br>s, <sub>max</sub> =<br>A <sub>h</sub> =<br>A <sub>v,min</sub> =<br>S = | 33<br>=<br>0.36<br>556<br>180<br>1111 | 0.36<br>0.5<br>m<br>mm²/m<br>mm²/m<br>mm | m   |

#### Calculation of the wall resistance and dimensions under axial loads



#### $A_v = 556 \text{ mm}^2/\text{m}$

#### Wall Axial Load Calculations Summary:

- Use 15M rebar for both vertical and horizontal reinforcement spaced at 300mm in both directions (NEED VERTS AT 150MM, SEE FOLLOWING)
- Wall is 120mm thick

#### Calculation of the Wall Resistance and Dimensions Under Flexural Loads

#### **Flexural Steel (vertical)**

|                                 | thickness       | t =                  | 0.12     | m     |
|---------------------------------|-----------------|----------------------|----------|-------|
| 15M reba<br>d <sub>b</sub> = 15 | ar<br>mm        | d =                  | 93       | mm    |
| 5                               | mm <sup>2</sup> | A <sub>s,req</sub> = | 1151     | mm2/m |
|                                 |                 | s <                  | 174      | mm    |
|                                 |                 | Choose<br>s =        | 150      | mm    |
| Proper reinforceme              | nt?             | A <sub>s</sub> =     | 1333.333 | mm²/m |
|                                 |                 | ρ =                  | 0.014414 |       |

#### Wall Flexural Load Calculations Summary:

• Use 15M reinforcement, vertical rebar to be spaced at 150mm



1.5
 2
 1.3
 1.3
 1.3
 1.3

#### **MSE Wall Calculations**

| radius                 |       |                   |                    |
|------------------------|-------|-------------------|--------------------|
| =                      | 3     | m                 | FS <sub>ID</sub> = |
| load =                 | 149   | kN                | FS <sub>CR</sub> = |
| Υ =                    | 18    | kN/m <sup>3</sup> | FS <sub>CD</sub> = |
| $\phi_{cs} =$          | 30    | deg               | FS <sub>BD</sub> = |
| $\phi_{cs} =$          | 0.52  | rad               | FS <sub>SP</sub> = |
| Ø <sub>b</sub> =       | 20    | deg               | FS <sub>T</sub> =  |
| Ø₅ =<br>Fail           | 0.35  | rad               |                    |
| Angle                  | 60    | deg               |                    |
| K <sub>ar</sub> =      | 0.33  |                   |                    |
| T <sub>ult</sub> =     | 58.6  | kN                |                    |
| T <sub>all</sub> =     | 11.56 | kN                |                    |
| Sz <sub>min</sub><br>= | 0.48  | m                 |                    |
| K <sub>ac</sub> =      | 0.30  |                   |                    |
| S <sub>u</sub> =       | 60.00 | kPa               |                    |
| S <sub>W</sub> =       | 30.00 | kPa               |                    |
| L <sub>b</sub> =       | 1.80  | m                 |                    |
| L <sub>b</sub> =       | 2.17  | m                 |                    |
| USE                    |       |                   |                    |
| L <sub>b</sub> =       | 2.17  | m                 |                    |



#### Table B-4- MSE Wall Dimensions

|       |            |       | 1.1.1   |       |                |                   |       |                    |                |     | Act    |
|-------|------------|-------|---------|-------|----------------|-------------------|-------|--------------------|----------------|-----|--------|
|       |            | •     | total σ | lat σ | max            | A                 | lat P | L <sub>r</sub> (m) | L <sub>e</sub> | L   | ual    |
| depth | σ<br>(kDa) | Δσ    | (kPa)   | (kPa) | S <sub>z</sub> | Actual            | (kN)  |                    | (m)            | (m) | L (ma) |
| (m)   | (kPa)      | (kPa) |         |       | (m)<br>1481    | Sz                |       |                    |                |     | (m)    |
|       |            |       | 0.00    |       | 818.           |                   |       |                    |                |     |        |
| 0.00  | 0.00       | 0.00  |         | 0.00  | 64             | 0.8               |       | 2.1                | 0.30           | 2.4 | 2.5    |
| 0.2   | 3.6        | 0.00  | 3.60    | 1.20  | 7.40           | 0.8               | 0.21  | 2.0                | 0.30           | 2.3 | 2.5    |
| 0.4   | 7.2        | 0.02  | 7.22    | 2.41  | 3.70           | 0.8               | 0.43  | 1.9                | 0.30           | 2.2 | 2.5    |
| 0.6   | 10.8       | 0.06  | 10.86   | 3.62  | 2.46           | 0.8               | 0.65  | 1.8                | 0.30           | 2.1 | 2.5    |
| 0.8   | 14.4       | 0.13  | 14.53   | 4.84  | 1.84           | 0.8               | 0.86  | 1.7                | 0.30           | 2.0 | 2.5    |
| 1     | 18         | 0.22  | 18.22   | 6.07  | 1.46           | 0.8               | 1.08  | 1.6                | 0.30           | 1.9 | 2.5    |
| 1.2   | 21.6       | 0.35  | 21.95   | 7.32  | 1.22           | 0.8               | 1.31  | 1.5                | 0.30           | 1.8 | 2.5    |
| 1.4   | 25.2       | 0.49  | 25.69   | 8.56  | 1.04           | 0.8               | 1.53  | 1.3                | 0.30           | 1.6 | 2.5    |
| 1.6   | 28.8       | 0.64  | 29.44   | 9.81  | 0.91           | 0.8               | 1.75  | 1.2                | 0.30           | 1.5 | 2.5    |
| 1.8   | 32.4       | 0.79  | 33.19   | 11.06 | 0.80           | 0.4               | 1.97  | 1.1                | 0.15           | 1.3 | 2.5    |
| 2     | 36         | 0.93  | 36.93   | 12.31 | 0.72           | 0.4               | 2.20  | 1.0                | 0.15           | 1.1 | 2.5    |
| 2.2   | 39.6       | 1.06  | 40.66   | 13.55 | 0.66           | 0.4               | 2.42  | 0.9                | 0.15           | 1.0 | 2.5    |
| 2.4   | 43.2       | 1.17  | 44.37   | 14.79 | 0.60           | 0.4               | 2.64  | 0.8                | 0.15           | 0.9 | 2.5    |
| 2.6   | 46.8       | 1.27  | 48.07   | 16.02 | 0.55           | 0.4               | 2.86  | 0.6                | 0.15           | 0.8 | 2.5    |
| 2.8   | 50.4       | 1.34  | 51.74   | 17.25 | 0.52           | 0.4               | 3.08  | 0.5                | 0.15           | 0.7 | 2.5    |
| 3     | 54         | 1.40  | 55.40   | 18.47 | 0.48           | 0.4               | 3.29  | 0.4                | 0.15           | 0.6 | 2.5    |
| 3.2   | 57.6       | 1.43  | 59.03   | 19.68 | 0.45           | 0.4               | 3.51  | 0.3                | 0.15           | 0.5 | 2.5    |
| 3.4   | 61.2       | 1.46  | 62.66   | 20.89 | 0.43           | 0.4               | 3.73  | 0.2                | 0.15           | 0.3 | 2.5    |
| 3.6   | 64.8       | 1.47  | 66.27   | 22.09 | 0.40           | 0.2               | 3.94  | 0.1                | 0.08           | 0.1 | 2.5    |
| 3.8   | 68.4       | 1.47  | 69.87   | 23.29 | 0.38           | 0.2               | 4.15  | 0.0                | 0.08           | 0.0 | 2.5    |
|       |            |       |         |       |                | P <sub>ax</sub> = | 41.6  | kN/m               |                |     |        |



| FS against        | bearing fa | ailure | <u>FS against</u> | overturning |          |      |
|-------------------|------------|--------|-------------------|-------------|----------|------|
| TSA               |            |        | Lat Pressu        | re Force    | 43.3     | kN/m |
| q <sub>u</sub> =  | 308.4      | kPa    | Lat Mome          | nt Arm      | 1.266667 | m    |
| FS <sub>B</sub> = | 4.51       |        | MSE Section       | on Weight   | 171      | kN/m |
|                   |            |        | Weight M          | oment Arm   | 1.25     | m    |
| ESA               |            |        |                   |             |          |      |
| horizontal        | 41.61      | kN/m   | FS <sub>o</sub> = | 3.9         |          |      |
| vertical          | 135        | kN/m   |                   |             |          |      |
| ω                 | 17.13      | deg    |                   |             |          |      |
| n =               | 2          |        |                   |             |          |      |
| i <sub>Υ</sub> =  | 0.33       |        |                   |             |          |      |
| Ν <sub>Υ</sub> =  | 22.46      |        |                   |             |          |      |
| q <sub>u</sub> =  | 171.96     |        |                   |             |          |      |
| FS <sub>B</sub> = | 2.46       |        |                   |             |          |      |



#### Calculation of Roof Slab Design Strip:

| 1. Input Loads         | M <sub>f</sub> =     | 180         |          |
|------------------------|----------------------|-------------|----------|
|                        | V <sub>f</sub> =     | 185         | kN       |
| 2. Minimum Thickness   | h =                  | 225         | mm       |
| USE:                   | h =                  | 250         | mm       |
| 3. Shear Design        | d =                  | 185         | mm       |
|                        | d <sub>v</sub> =     | 167         | mm       |
|                        | β =                  | 0.197       |          |
|                        | -                    |             |          |
|                        | V <sub>c</sub> =     | 117.1       | kN       |
| V <sub>c</sub> <       | $V_{\rm f}$          | *Stirrups F | Required |
|                        | V <sub>s</sub> Req = | 68          | kN       |
| Assuming 10M Stirrups: |                      |             |          |
|                        | Av =                 | 200         | mm       |
|                        | s =                  | 238         | mm       |
| USE:                   | s =                  | 200         | mm       |
|                        | Smax =               | 117         | mm       |
| USE:                   | s =                  | 100         | mm       |
|                        | Av Min =             | 82          | mm       |
|                        | V <sub>s</sub> =     | 162         | kN       |
|                        | V <sub>r</sub> =     | 279         | kN       |
| V <sub>f</sub> <       | Vr                   | *Good       |          |
|                        | $V_r / V_f =$        | 1.51        | > 1.20   |
| 4. Moment Resistance   | Kr =                 | 5.26        |          |



|                         |           | As Req = | 3682  | mm² |  |
|-------------------------|-----------|----------|-------|-----|--|
| Select 25M @ 120mm      | n O/C:    |          |       |     |  |
|                         |           | As =     | 4176  | mm² |  |
| A <sub>s</sub> Req'd    | <         | As       | *Good |     |  |
|                         |           | As Min = | 500   | mm² |  |
| A <sub>s</sub> Min      | <         | As       | *Good |     |  |
| 5. Transverse Steel     |           | As Min = | 684.6 | mm² |  |
| Select 20M @ 420mm      | n O/C:    |          |       |     |  |
|                         |           | As =     | 714   | mm² |  |
| A <sub>s</sub> Min      | <         | As       | *Good |     |  |
| Γ                       |           |          |       |     |  |
| 1m Design Strip Summary | y:        |          |       |     |  |
| Slab to have thickness  | s of 250m | m        |       |     |  |

- Longitudinal Rebar to be 25M @ 120mm o/c
- Transverse Rebar to be 20M @ 420mm o/c
- Stirrups in Longitudinal Direction to be 10M @ 100mm o/c



## Appendix C: 2016 MOTI Standards for Highway Construction Specifications

#### Concrete:

- The contractor shall comply with the standards listed below and be responsible for quality control of all components of the concrete operation, including but not limited to, aggregate and component quality, proportioning, test batching, batching, mixing, transporting, placing, consolidating, finishing, curing, and all necessary quality control and verification testing of the components and the fresh and hardened concrete.
- The Contractor shall be responsible for proportioning and designing all concrete in full compliance with the concrete mix parameters as listed in the 2016 MOTI 2016 Standards for Highway Construction. All mix designs shall use the "Absolute-Volume Method" for mix proportioning.
- 3. The Contractor shall submit a report outlining the proposed mix design for each classification of concrete to the UBC Campus and Community Planning (the Owner) Representative for review and acceptance at least 2 weeks in advance of when concrete production is scheduled to commence. Acceptance of the mix design by the Owner does not constitute acceptance of the concrete. Acceptance of the concrete will be based on the test results and the performance and quality of the concrete and concrete components placed on the project. No concrete shall be placed prior to receiving the Owner's acceptance of the mix design. Each mix design submittal shall contain the standard components listed in the 2016 MOTI 2016 Standards for Highway Construction.
- 4. Aggregate gradation shall fall within the envelopes specified in Tables 211-B and 211-C



#### Table 211-B GRADATION REQUIRMENTS FOR COARSE AGGREGATES

| NMS<br>A <sup>(1)</sup> | Product<br>Size     |      |        | Total Pa | ssing Each | Sieve, Pei | rcentage b | y Mass |       |        |
|-------------------------|---------------------|------|--------|----------|------------|------------|------------|--------|-------|--------|
| (mm)                    | (mm)                | 56mm | 40mm   | 28mm     | 20mm       | 14mm       | 10mm       | 5mm    | 2.5mm | 1.25mm |
| 40                      | 40-5 <sup>(2)</sup> | 100  | 95-100 | -        | 35-70      | -          | 10-30      | 0-5    | -     | -      |
| 28                      | 28-5 <sup>(2)</sup> | -    | 100    | 95-100   | 63-83      | 30-65      | -          | 0-10   | 0-5   | -      |
| 20                      | 20-5                | -    | -      | 100      | 90-100     | 50-90      | 25-60      | 0-10   | 0-5   | -      |
| 14                      | 14-5                | -    | -      | -        | 100        | 90-100     | 45-75      | 0-15   | 0-5   | -      |
| 10                      | 10-2.5              | -    | -      | -        | -          | 100        | 85-100     | 10-30  | 0-5   | 0-5    |

(1) NMSA – nominal maximum size of course aggregate. Definition: The standard Sieve size opening immediately smaller than the smallest through which all of the aggregate must pass.

(2) To prevent segregation, aggregates that make up the above gradings shall be stockpiled and batched in two or more separate sizes as per CSA A23.1

#### TABLE 211-C GRADATION REQUIREMENTS FOR FINE AGGREGATES

| SIEVE<br>SIZE<br>(mm) | TOTAL<br>CUMULATIVE<br>PASSING EACH<br>SIEVE,<br>PERCENTAGE<br>BY<br>MASS | SIEVE<br>SIZE<br>(mm) | TOTAL<br>CUMULATIVE<br>PASSING EACH<br>SIEVE,<br>PERCENTAGE<br>BY<br>MASS |
|-----------------------|---|-----------------------|---|
| 10                    | 100   | 0.630                 | 25-65   |
| 5                     | 95-100  | 0.315                 | 10-35   |
| 2.5                   | 80-100  | 0.160                 | 2-10  |
| 1.25                  | 50-90   |                       |   |

- All <u>materials</u> shall comply with:
  - CAN/CSA A23.1 Concrete materials and methods of concrete construction
  - o CAN/CSA A3000 Cementitious Materials Compendium
- <u>Field tests</u> shall conform to:
  - o CAN/CSA A23.2 Test Methods and standard practices for concrete



- Formwork shall be designed and constructed in accordance with:
   CAN/CSA S269.3 Concrete Formwork
- <u>Lab testing</u> shall adhere to:
  - CAN/CSA A283 Qualification Code for Concrete Testing Laboratories

#### Earthworks:

- All <u>material testing</u> shall be performed according to the following standards:
  - ASTM C127 Test Method for Density, Relative Density (Specific Gravity) and Absorption of Coarse Aggregate
  - ASTM D422 Standard Method of Particle-Size Analysis of Soils
  - ASTM D698 Test Method for Laboratory Compaction Characteristics of Soil Using Standard Effort
  - ASTM D1140 Test Method for Amount of Material in Soils Finer than the No. 200 Sieve
  - ASTM D4318 Test Method for Liquid Limit, Plastic Limit, and Plasticity Index of Soils
- <u>Field compaction testing</u> shall adhere to the following standards (Nuclear Methods preferred):
  - ASTM D1556 Test Method for Density of Soil in Place by the Sand-Cone Method
  - ASTM D2167 Test Method for Density of Soil in Place by the Rubber-Balloon Method
  - ASTM D2922 Test Methods for Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth)
  - ASTM D3017 Test Method for Water Content of Soil and Rock in Place by Nuclear Methods (Shallow Depth)

#### Site Grading:

- The earth embankment shall be constructed in successive horizontal layers not exceeding 200 mm in loose thickness except that the top 500 mm shall be constructed in layers not exceeding 100 mm in loose thickness. Each layer shall be compacted to minimum 95% of the Standard Proctor Density obtained by the current ASTM D 698, except in the top 300 mm of the embankment, which shall be compacted to minimum 100% of the Standard Proctor Density.
- No organic soils shall be placed in the embankment. Soils with high moisture content that cannot be compacted to the required density shall not be employed without prior aeration and drying.



- 3. Borrow shall consist of rut resistant material, with less than 20% passing the 0.075 mm sieve and free of organics, high plasticity clays and other unsuitable materials, obtained from an approved source of supply (e.g. pit or quarry) outside the highway right-of way.
- 4. Aggregates for surfacing, base, subbase and bridge end fill will be tested in accordance with the tests listed in Table 202-A.

| Based on<br>ASTM | Title of Test               |  |  |  |  |  |  |  |
|------------------|-----------------------------|--|--|--|--|--|--|--|
| C 136            | Sieve Analysis of Fine and  |  |  |  |  |  |  |  |
| C 150            | Coarse Aggregates           |  |  |  |  |  |  |  |
| C 117            | Wash Test of Aggregates     |  |  |  |  |  |  |  |
|                  | Soundness of Aggregate by   |  |  |  |  |  |  |  |
| C 88             | Use                         |  |  |  |  |  |  |  |
|                  | of Magnesium Sulphate.      |  |  |  |  |  |  |  |
|                  | Standard Test Method for    |  |  |  |  |  |  |  |
|                  | Sand                        |  |  |  |  |  |  |  |
| D 2419           | Equivalent Value of Soils   |  |  |  |  |  |  |  |
|                  | and                         |  |  |  |  |  |  |  |
|                  | Fine Aggregate              |  |  |  |  |  |  |  |
| D 6928           | Abrasion Loss by Micro-     |  |  |  |  |  |  |  |
| 0.0520           | Deval                       |  |  |  |  |  |  |  |
| D 4318           | Plastic Limit Determination |  |  |  |  |  |  |  |
| BASED ON<br>MOT  | Title of Test               |  |  |  |  |  |  |  |
| SS 202           | Fracture Count on Coarse    |  |  |  |  |  |  |  |
| Appendix 1       | Aggregate                   |  |  |  |  |  |  |  |
| SS 202           | Detrographic Test           |  |  |  |  |  |  |  |
| Appendix 2       | Petrographic Test           |  |  |  |  |  |  |  |

#### TABLE 202-A: AGGREGATE QUALITY TESTS

5. All aggregates for surfacing, base, subbase, and bridge end fill shall meet the requirements of Table 202-B.



|                                  |                         |                   |                   | Test Res          | ult   |                   |                   |       |  |  |
|----------------------------------|-------------------------|-------------------|-------------------|-------------------|-------|-------------------|-------------------|-------|--|--|
| TEST                             | Surfacing<br>Aggregates | Ba                | se Aggregates     |                   |       |                   |                   |       |  |  |
|                                  | HFSA                    | 25mm              | 50mm              | 75mm              | SGSB  | IGSB              | OGSB              | BEF   |  |  |
| Sand<br>Equivalent               | ≥ 20                    | ≥ 40              | ≥ 40              | ≥ 40              | ≥ 20  | ≥ 20              | ≥ 20              | ≥ 20  |  |  |
| Micro-Deval<br>loss factor       | ≤ 25%                   | ≤ 25%             | ≤ 25%             | ≤ 17%             | ≤ 30% | ≤ 25%             | ≤ 25%             | ≤ 30% |  |  |
| Fractured<br>Faces<br>Method "A" | ≥ 50 <sup>1</sup>       | ≥ 50 <sup>1</sup> | ≥ 50 <sup>1</sup> | ≥ 50 <sup>1</sup> | n/a   | ≥ 50 <sup>1</sup> | ≥ 50 <sup>1</sup> | n/a   |  |  |
| Plasticity                       | ≤ 6                     | n/a               | n/a               | n/a               | n/a   | n/a               | n/a               | n/a   |  |  |

#### TABLE 202-B: AGGREGATE PROPERTIES

<sup>1</sup>Values are for total sample.

6. Aggregate shall have a gradation that defines a curve (% passing versus log sieve size) with a slope between adjacent sieves, equal or intermediate to the corresponding slopes of the boundary curves defined by the specification. Gradations shall fall within the limits, for the specified classification, shown in Table 202-C.



#### Table 202-C: Aggregate Gradations

|               |                            |             |             |             |             | Perce       | nt Passing  | (%) Sieve S | Size        |             |             |                    |                    |             |
|---------------|----------------------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|--------------------|--------------------|-------------|
| Sieve<br>Size | Surfacing<br>Aggregat<br>e |             |             |             | В           | ase Course  | 2           |             |             | Subb        | gates       | Bridge<br>End Fill |                    |             |
| (mm)          |                            |             | WGB         |             |             | IGB         |             |             | OGB         |             |             | 1000               |                    | 255         |
|               | HFSA                       | 25mm        | 50mm        | 75mm        | 25mm        | 50mm        | 75mm        | 25mm        | 50mm        | 75mm        | SGSB        | IGSB               | OGSB               | BEF         |
| 75            |                            |             |             | 100         |             |             | 100         |             |             | 100         | 100         | 100                | 100                | 100         |
| 50            |                            |             | 100         |             |             | 100         | 55 -<br>100 |             | 100         | 70 -<br>100 |             | 55 -<br>100        | <u>70</u> -<br>100 | 30 -<br>100 |
| 37.5          |                            |             | 80 -<br>100 | 60 -<br>100 |             | 60 -<br>100 | 40 - 80     |             | 75 -<br>100 | 50 - 85     |             | 40 - 80            | 50 - 85            |             |
| 25            | 100                        | 100         |             |             | 100         | 40 - 75     |             | 100         |             |             |             |                    |                    |             |
| 19            | 85 - 100                   | 80 -<br>100 | 50 -<br>100 | 35 - 80     | 65 -<br>100 |             | 17 - 40     | 75 -<br>100 | 35 - 65     | 15 - 55     | 15 -<br>100 | 17 - 40            | 15 - 55            | 20 -<br>100 |
| 12.5          |                            |             |             |             |             | 15 - 40     |             |             |             |             |             |                    |                    |             |
| 9.5           | 60 - 85                    | 50 - 85     | 35 - 75     | 25 - 60     | 30 - 70     |             |             | 30 - 65     | 5 - 35      |             | 0 - 100     |                    |                    |             |
| 6.3           |                            |             |             |             |             |             |             |             |             | 0 - 20      |             |                    | 0 - 20             |             |
| 4.75          | 40 - 70                    | 35 - 70     | 25 - 55     | 20 - 40     | 15 - 40     |             |             | 5 - 30      | 0 - 15      |             |             |                    |                    | 10 - 60     |
| 2.36          |                            | 25 - 50     | 20 - 40     | 15 - 30     | 10 - 30     | 10 - 25     | 10 - 25     | 0 - 10      | 0 - 10      | 0 - 10      |             | 10 - 25            | 0 - 10             |             |
| 1.18          | 20 - 50                    | 15 - 35     | 15 - 30     | 10 - 20     |             |             |             |             |             |             |             |                    |                    | 6 - 32      |
| 0.60<br>0     |                            |             |             |             |             |             |             |             |             |             | 0 - 100     |                    |                    |             |
| 0.30<br>0     | 10 - 30                    | 5 - 20      | 5 - 15      | 3 - 10      | 5 - 15      | 5 - 15      | 4 - 15      | 0 - 8       | 0 - 8       | 0 - 8       | 0 - 15      | 4 - 15             | 0 - 8              | 4 - 15      |
| 0.07<br>5     | 5 - 15                     | 0 - 5       | 0 - 5       | 0 - 5       | 0 - 5       | 0 - 5       | 0 - 5       | 0 - 5       | 0 - 5       | 0 - 5       | 0 - 5       | 0 - 5              | 0 - 5              | 0 - 5       |



7. Aggregates for subbase shall be delivered to the roadbed as uniform mixtures and shall be spread in layers without segregation, preferably through an approved aggregate spreader. Granular aggregate shall not be end dumped from trucks in piles on the grade. The Owner may permit spreading from the tailgate of trucks or from centre dump units, provided the Owner is satisfied that the work will be well controlled and segregation will not occur.

8. Immediately following spreading, the material shall be compacted to a minimum 100% of the Standard Proctor Density obtained by the current ASTM D 698.

9. The crushed base course shall be constructed in such a manner that the aggregate is neither segregated, contaminated nor degraded. End dumping will not be permitted. The thickness of the crushed base course shall be substantially uniform and the minimum thickness shall not be less than the nominal thickness shown on the Drawings or ordered by the Owner. If the Contractor is unable to provide adequate manually

operated equipment or workers of sufficient skill to lay the crushed base course aggregate within the tolerances specified, the Owner may require that the Contractor lay the aggregate through an approved electronically controlled spreading machine.

10. Immediately following spreading, the crushed base course aggregate shall be compacted to a minimum 100% of the Standard Proctor Density obtained by the current ASTM D 698.

#### **CULVERTS**

- The embedment material shall be placed and compacted in lifts not exceeding 200 mm compacted thickness, with each lift compacted to a minimum of 95% of Standard Proctor Density prior to addition of the next lift. The bedding layer of a 200 mm thickness in direct contact with the invert shall be shaped to the pipe culvert curved invert and shall be left uncompacted.
- The embedment material within 300 mm of the pipe culvert walls shall be free of stones exceeding 75 mm size. Heavy equipment shall not be allowed within 1 m of the pipe culvert walls.

#### <u>RIPRAP</u>

- 1. Class 10 riprap shall be used.
- 2. Rock shall be hard, durable, and angular quarry rock of a quality that will not disintegrate on exposure to water or the atmosphere.

51 | Page



- Property **Test Designation Allowable Value** ≥ 2.60 Specific Gravity ASTM D6473 Absorption ASTM D6473 ≤ 1% Soundness by use ≤ 10% (following of Magnesium **ASTM D5240** 5 cycles) Sulphate Micro-Deval Abrasion Loss ASTM D6928 ≤ 20% Factor
- 3. Riprap shall meet the following quality requirements:

#### **FENCE**

- 1. Fence shall be of Type D Chain Link Fence
- 2. Fence materials shall adhere to the following specifications

| CAN/CGSB-<br>138.1-M<br>and 1-GP-<br>181M | Fence, Chain Link, Fabric Coating, Zinc-Rich, Organic, Ready Mixed   |
|---|--|
| ASTM A 53                                 | Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated Welded and<br>Seamless                              |
| ASTM A 90                                 | Test Method for Weight of Coating on Zinc-Coated (Galvanized) Iron or Steel<br>Articles                              |
| ASTM A 116                                | Specification for Zinc-Coated (Galvanized) Steel Woven Wire Fence Fabric   |
| ASTM A 121                                | Specification for Zinc-Coated (Galvanized) Steel Barbed Wire   |
| ASTM A 123                                | Specification for Zinc (Hot-Galvanized) Coatings on Products Fabricated from<br>Rolled,<br>Pressed, and Forged Steel |
| ASTM A 153                                | Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware  |
| ASTM A 641                                | Specification for Zinc-Coated (Galvanized) Carbon Steel Wire   |
| ASTM B 6                                  | Specification for Zinc (Slab Zinc)   |
| ASTM B<br>211M                            | Specification for Aluminum-Alloy Bar, Rod, and Wire [Metric]   |



#### FOUNDATION EXCAVATION

- All materials shall be removed as necessary for the construction of foundations or other works. Foundation excavations shall not be larger than is reasonably necessary. Excavations and adjacent highways and other facilities shall be protected as necessary by barricades, shoring, dykes and/or cofferdams. Excavations shall be constructed in compliance with the applicable Workers Compensation Act, Occupational Health and Safety Regulations, BC.
- 2. Care shall be taken not to disturb the bottom of the excavation. If the bottom of the excavation is disturbed in material other than rock, the Contractor shall remove and dispose of all disturbed material and shall replace it with suitable soil at the direction of the Owner. If the bottom of the excavation is disturbed in rock, the Contractor shall remove and dispose of all disturbed material and shall replace it with suitable soil at the direction shall remove and dispose of all disturbed in rock, the contractor shall remove and dispose of all disturbed material and shall replace it with a concrete sub-footing, as directed by the Owner.
- 3. After the structures are sufficiently built, excavations shall be backfilled to the original ground contours with excavated material, as directed by the Owner, unless this material is designated as unsuitable.
- 4. Drainage course material shall be installed as shown on the Drawings. The gradation of the drainage course materials shall be as follows:

| Sieve Size (mm) | % Passing By Mass |
|-----------------|-------------------|
| 40              | 100               |
| 20              | 0-100             |
| 10              | 0                 |

#### **DESIGN STANDARDS USED:**

Reinforced Concrete:

• CSA A23.3-14

Tunnel and loading scheme used for road components:

• CSA S6-06

MSE Wall:

- Canadian Foundation Engineering Manual
- Nilex
- Budhu

Road design:

- NCHRP 672 Roundabouts: An Informational Guide
- BC Supplement to TAC Geometric Guidelines
- NACTO Urban Bikeway Design Guide

Signage:



- BC Ministry of Transportation and Highways Manual of Standard Traffic Signs & Pavement Markings
- Transportation Association of Canada Manual of Uniform Control Devices for Canada

LID:

• Metro Vancouver Stormwater Source Control Design Guidelines 2012

\*\*\*Design of traditional stormwater infrastructure was performed with the rational method

\*\*\*Lawn basins typical MMCD



# Appendix D: Detailed Design Construction Schedule

| -  |     |        |  |      |  |     |  | 20 | 18  |   |     |   |   |    |         |  |  |   |     | 2019 |  |   |    |           |  |
|--|-----|--------|--|------|--|-----|--|----|-----|---|-----|---|---|----|---------|--|--|---|-----|------|--|---|----|-----------|--|
| Task   | MAY | / JUNE |  | JULY |  | AUG |  |    | SEP | 2 | 001 | Γ | Γ | NO | IOV DEC |  |  | С | JAN |      |  |   | FE | В         |  |
| Project Tendering                                      |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  | Т |    |           |  |
| Request for Proposal                                   |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Bid Period   |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Project Awarded  |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| General Site Preparation & Crew Orientations           |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Site Fencing & Traffic Control Setup                   |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Job Trailers and Equipment Delivery                    |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Site Orientations                                      |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Corridor Construction: Drummond Dr - Acadia Rd         |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Corridor Segment 1: Roundabout Construction            |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Decommission Existing Intersection                     |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Install New CB's & Complete Drainage Tie-Ins           |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Backfill, Sub-Base, & Base Installation & Compaction   |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Install Curbing  |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Paving   |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Install Road Markings, & Temporary & Permanent Signage |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    | $\square$ |  |
| Corridor Segment 2: Drummond Dr - Acadia Rd            |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Removal of Existing Pavement & Drainage Infrastructure |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Install Pedestrian Underpass                           |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Install New CB's & Complete Drainage Tie-Ins           |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    | $\square$ |  |
| Install Lighting and Ducting for Pedestrian Crossings  |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Backfill, Sub-Base, & Base Installation & Compaction   |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Install Curbing  |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    | $\square$ |  |
| Paving   |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Install Road Markings, & Temporary & Permanent Signage |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Corridor Segment 3: Bioswale Construction              |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Removal of Existing Pavement & Drainage Infrastructure |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Grading  |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Installation of Drainage Infrastructure                |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Backfill, Compaction & Sod Installation                |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Vegatation Installation                                |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Multi-Purpose Trail Construction                       |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| General Landscaping, Fencing, & Aethetics              |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Project Wrap-Up  |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Project Deficiencies                                   |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Site Clean-Up and Removal of Job Trailers & Equipment  |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| Comissioning of Corridor                               |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |
| As-Built Drawings                                      |     |        |  |      |  |     |  |    |     |   |     |   |   |    |         |  |  |   |     |      |  |   |    |           |  |



# Appendix E: Detailed Construction Cost

| DESCRIPTION OF WORK  | UoM          | QTY  | Unit Price   | Total Amt    |
|--|--------------|------|--------------|--------------|
|  |              |      |              |              |
| DIVISION 01 - GENERAL REQUIREMENTS   |              |      |              |              |
| Traffic Control, Vehicle Access and Parking                                      |              |      |              |              |
| Traffic Control, Vehicle Access and Parking - Phase 1 (Roundabout and Underpass) | L.S.         | 1    | \$40,000.00  | \$40,000.00  |
| Traffic Control, Vehicle Access and Parking - Phase 2 (Corridor)                 | L.S.         | 1    | \$10,000.00  | \$10,000.00  |
| Dynamic Message Signs  | Sign / wk    | 40   | \$350.00     | \$14,000.00  |
| Environmental Proteciton   |              |      |              |              |
| Environmental Protection - Phase 1   | L.S.         | 1    | \$30,000.00  | \$30,000.00  |
| Environmental Protection - Phase 2   | L.S.         | 1    | \$5,000.00   | \$5,000.00   |
| Total Division 01  |              |      |              | \$99,000.00  |
|  |              |      |              |              |
| DIVISION 03 - CONCRETE   |              |      |              |              |
| Pedestrian Underpass   |              |      |              |              |
| Cast-in-Place Construction   | Lump Sum     | 1    | \$100,000.00 | \$100,000.00 |
| Concrete Walks, Curb and Gutter  |              |      |              |              |
| Barrier Curb and Gutter, MMCD C4   | Lineal Metre | 3600 | \$110.00     | \$396,000.00 |
| Rollover Curb and Gutter, MMCD C4  | Lineal Metre | 94   | \$90.00      | \$8,460.00   |
| 1.4.4 Median Curb, SSD-R.15.3 c/w Key  | Lineal Metre | 100  | \$70.00      | \$7,000.00   |
| 100mm Thickness, Broom Finished Sidewalk   | Square Metre | 1050 | \$100.00     | \$105,000.00 |
| 150mm Thickness, Red stamped concrete  | Square Metre | 462  | \$270.00     | \$124,740.00 |
| Bioswale Weirs   | Cubic Metre  | 7.32 | \$300.00     | \$2,196.00   |
| Total Division 03  |              |      |              | \$743,396.00 |
|  |              |      |              |              |



| DIVISION 26 - ELECTRICAL                   | 1            |       |              |              |
|--|--------------|-------|--------------|--------------|
| Roadway Lighting                           |              |       |              |              |
|  |              | 1     | ¢100.000.00  | ¢100.000.00  |
| Roadway Lighting for roundabout and tunnel | L.S.         | 1     | \$100,000.00 | \$100,000.00 |
| Total Division 26                          |              |       |              | \$100,000.00 |
|  |              |       |              |              |
| DIVISION 31 - EARTHWORK                    |              |       |              |              |
| Clearing and Grubbing                      |              |       |              |              |
| Clearing and Grubbing                      | Lump Sum     | 1     | \$50,000.00  | \$50,000.00  |
| Reshaping Granular Roadbed                 |              |       |              |              |
| Reshaping Granular Roadbed                 | Square Metre | 10750 | \$2.25       | \$24,187.50  |
| Common Excavation                          |              |       |              |              |
| Common Excavation - Off-Site Disposal      | Cubic Metre  | 12000 | \$25.00      | \$300,000.00 |
| Common Excavation - On-Site Reuse          | Cubic Metre  | 5914  | \$25.00      | \$147,850.00 |
| Gabions                                    |              |       |              |              |
| Sierra Scape Wall c/w Vegetated Face       | Square Metre | 740   | \$400.00     | \$296,000.00 |
| Rip Rap                                    |              |       |              |              |
| Class 10 Rip Rap (Bioswales)               | Tonne        | 1350  | \$70.00      | \$94,500.00  |
| Total Division 31                          |              |       |              | \$912,537.50 |
|  |              |       |              |              |
| DIVISION 32 - ROADS AND SITE IMPROVEMENTS  |              |       |              |              |
| Cold Milling                               |              |       |              |              |
| 50-75mm Depth (surface) milling            | Square Metre | 10750 | \$6.00       | \$64,500.00  |
| Granular Subbase                           |              |       |              |              |
| 75mm Minus Select Granular Subbase         | Tonne        | 7200  | \$20.00      | \$144,000.00 |
| Granular Base                              |              |       |              |              |
| 19mm Minus Granular Base                   | Tonne        | 3600  | \$25.00      | \$90,000.00  |



| Hot-Mix Asphalt Concrete Paving   |               |       |              |                |
|---|---------------|-------|--------------|----------------|
|   | Tanna         | 1950  | \$100.00     | ¢105.000.00    |
| Asphalt Pavement - Lower Course #2  | Tonne         |       |              | \$195,000.00   |
| Asphalt Pavement - Upper Course #2  | Tonne         | 3890  | \$110.00     | \$427,900.00   |
| Porous Asphalt Path, no concrete curb   | Square Metre  | 3,840 | \$40.00      | \$153,600.00   |
| Painted Pavement Markings   |               |       |              |                |
| Standard Bike and Traffic Lane Markings (≈2km)  | Lump Sum      | 1     | \$300,000.00 | \$300,000.00   |
| Permanent Thermoplastic Pavement Markings   | Lump Sum      | 1     | \$30,000.00  | \$30,000.00    |
| Enhanced Safety Markings  | Lump Sum      | 1     | \$10,000.00  | \$10,000.00    |
| Signage   |               |       |              |                |
| BC MoT and CoV Standard Traffic Signs (installed)                                       | ea            | 40    | \$500.00     | \$20,000.00    |
| Fences & Gates  |               |       |              |                |
| Cedar Tie Fencing   | Lineal Metre  | 950   | \$50.00      | \$47,500.00    |
| 1200mm High Steel Handrail MMCD C14, Powder Coated Black, Embedded Mounting in Sidewalk | Lineal Metre  | 200   | \$70.00      | \$14,000.00    |
| Imported Topsoil  | Cubic Metre   | 2884  | \$40.00      | \$115,344.00   |
| Hydraulic Seeding   |               |       |              |                |
| Hydraulic Seeding   | Square Metre  | 7500  | \$1.00       | \$7,500.00     |
| Sodding   |               |       |              |                |
| Nursery Sod   | Square Metres | 4500  | \$9.00       | \$40,500.00    |
| Total Division 32   |               |       |              | \$1,659,844.00 |
|   |               |       |              |                |
| DIVISION 33 - UTILITIES   |               |       |              |                |
| Storm Sewer   |               |       |              |                |
| 150mm diameter PVC  | Lineal Metre  | 700   | \$70.00      | \$49,000.00    |
| Pipe Culvert  |               |       |              |                |
| Concrete Box Culvert (Wildlife Crossing) - 1800mm x 900mm (including natural substrate) | Lineal Metre  | 22    | \$3,000.00   | \$66,000.00    |
| Concrete Box Culvert 4500mm x 2500mm Pedestrian Underpass                               | Lineal Metre  | 15    | \$15,000.00  | \$225,000.00   |

| Campus Consulting Ltd. |  | Corridor Redesign of Chancellor Boulevard<br>Detailed Design Report<br>Campus Consulting Ltd.<br>April 10, 2018 |
|------------------------|--|---|
| Total Division 32      |  | \$340,000.00  |
|                        |  |   |

# **GRAND TOTAL**

\$3,854,777.50




# CHANCELLOR BOULEVARD CORRIDOR DETAILED DESIGN

# BRITISH COLUMBIA Ministry of Transportation and Infrastructure




Campus Consulting Ltd. 12324 70° Street, Vancouver, BC




| SCALE    | 0 100 1:10,000 500m CAD FILENAME<br>PLOT DATE |      | BRITISH<br>COLUMBIA<br>SOL      |   | 001<br>CHANCELLOR BOUL |                               |     |                 |
|----------|---|------|---------------------------------|---|------------------------|-------------------------------|-----|-----------------|
| REV DATE | REVISIONS                                     | NAME | HIGHWAY EN                      | JTH COAST REGION  |                        | CORRIDOR REDE<br>SITE LOCATIO |     |                 |
| A        |   |      |                                 | DESIGNED BK DATE2017-11-26  |                        |                               |     |                 |
|          |   |      |                                 | QUALITY CONTROL         SM         DATE         2017-11-26           QUALITY ASSURANCE         CP         DATE         2017-11-26 | FILE NUMBER            | PROJECT NUMBER                | REG | DRAWING NUMBER  |
|          |   |      | SENIOR DESIGNER DATE 2017-11-26 | DRAWN BK_DATE2017-11-26   | N/A                    | N/A                           | 1   | C0-000 -<br>001 |

# DRAWINGS


- 100-105 PLAN
- 201-203 PROFILE
- 301-302 TYPICAL DETAILS
- 601-604 STORM PLAN & PROFILE
- S-101-103 STRUCTURAL DRAWINGS



|  |                 | DESIGNED          | BK DA        |
|--|-----------------|-------------------|--------------|
|  |                 | DESIGNED          |              |
|  |                 | QUALITY CONTROL   | <u>SM</u> DA |
|  | SENIOR DESIGNER | QUALITY ASSURANCE | CP DA        |
|  | SENIOR DESIGNER |                   |              |
|  | DATE 2017-11-26 | DRAWN             | <u>BK</u> DA |
|  |                 |                   |              |




|   | SCA | ALE . | PLOT DATE | 4/10/2018 |                 | FRASTRUCTURE<br>H COAST REGION |
|---|-----|-------|-----------|-----------|-----------------|--------------------------------|
| F | REV | DATE  | REVISIONS | NAME      | HIGHWAY ENGI    | NEERING AND GEOMAT             |
|   | А   |       |           |           |                 | DESIGNED                       |
|   |     |       |           |           |                 | QUALITY CONTROL                |
|   |     |       |           |           | SENIOR DESIGNER | QUALITY ASSURANCE              |
|   |     |       |           |           | DATE 2017-11-26 | DRAWN                          |




| BIA  |                                 |
|------|---------------------------------|
| DIII | SOUTH COAST REGION              |
|      | HIGHWAY ENGINEERING AND GEOMATI |


| REV | DATE | REVISIONS | NAME | HIGHWAY ENGINEERING AND GEOMATICS |  |  |  |  |
|-----|------|-----------|------|-----------------------------------|--|--|--|--|
| А   |      |           |      |                                   |  |  |  |  |
|     |      |           |      |                                   | DESIGNED <u>BK</u> D<br>QUALITY CONTROL SM D |  |  |  |
|     |      |           |      | SENIOR DESIGNER                   | QUALITY ASSURANCE D                          |  |  |  |
|     |      |           |      | DATE 2017-11-26                   | DRAWN <u>BK</u> D                            |  |  |  |



|                 | DEGIONED          | BK DA        |
|-----------------|-------------------|--------------|
|                 | DESIGNED          | <u> </u>     |
|                 | QUALITY CONTROL   | <u>SM</u> DA |
|                 | QUALITY ASSURANCE | CP DA        |
| SENIOR DESIGNER |                   |              |
| DATE 2017-11    | 1-26 DRAWN        | <u> </u>     |




|  |                 | DEGLONED          | BK I |
|--|-----------------|-------------------|------|
|  |                 | DESIGNED          |      |
|  |                 | QUALITY CONTROL   | SM I |
|  |                 |                   |      |
|  | SENIOR DESIGNER | QUALITY ASSURANCE | CP   |
|  |                 | DRAWN             | BK I |
|  | DATE 2017-11-26 |                   |      |
|  |                 |                   |      |



|          |                              |                                | PROPOSE                      | D PEDESTRIAN | UNDERPASS        |             |   |                              |               |         |       |               |
|----------|------------------------------|--------------------------------|------------------------------|--------------|------------------|-------------|---|------------------------------|---------------|---------|-------|---------------|
|          | STA 0+241.262<br>PIVC 76.833 |                                | STA 0+290.000<br>PIVC 76.492 |              | 38 V<br>K 13<br> |             |   | 76 VC<br>K 20.0              | EVC 0+451.731 | EXISTIN |       |               |
| 2/0      |                              | -0,70%                         |                              |              |                  | -0.50       | % |                              |               | t       | 3.30% | 09            |
| -210.012 |                              | EVC 0+266.612<br>BVC 0+272.450 |                              | 0+307.550    |                  |             |   |                              |               |         |       | BVC 0+522.560 |
|          | 51 VC<br>K 13.0              | EVC 0+<br>BVC 0+               | 35 VC<br>K 13.0              | EVC 0+0      | STA 0+349.023    | 71VC /4.400 |   | STA 0+413.731<br>PIVC 74.162 |               |         |       |               |


| SC  | ALE  | 0 10 | H 1:1000<br>V 1:100 | 50m<br>5m | CAD FILENAME<br>PLOT DATE | C0-200<br>4/10/2018 | BRITISH<br>COLUMBLA | AND INF | F TRANSPORTA<br>FRASTRUCTUR | E       |            |
|-----|------|------|---------------------|-----------|---------------------------|---------------------|---------------------|---------|-----------------------------|---------|------------|
| REV | DATE |      | REV                 | /ISIONS   |                           | NAME                |                     |         | IEERING AND GEO             |         |            |
| А   |      |      |                     |           |                           |                     |                     |         |                             |         |            |
|     |      |      |                     |           |                           |                     |                     |         | DESIGNED                    | BK DATE | 2017-11-26 |
|     |      |      |                     |           |                           |                     |                     |         | QUALITY CONTROL             | SM DATE | 2017-11-26 |
|     |      |      |                     |           |                           |                     | SENIOR DESIGNER     |         | QUALITY ASSURANCE           | CP DATE | 2017-11-26 |
|     |      |      |                     |           |                           |                     | DATE 2017-11-26     |         | DRAWN                       | BK DATE | 2017-11-26 |



### PROFILE

STA. 0+000.000 TO 0+720.000

| SM DATE 2017-11-26 |             |                |     |                |     |
|--------------------|-------------|----------------|-----|----------------|-----|
| CP DATE 2017-11-26 | FILE NUMBER | PROJECT NUMBER | REG | DRAWING NUMBER | REV |
| BK DATE 2017-11-26 | ΝΙ/Λ        | N/A            | 1   | C0-200         |     |
| BK DATE            |             |                | •   | 00 200         |     |



0

| SC | ALE | 0 1 V 1:100 5m |  | <u>C0-200</u><br><u>4/10/2018</u><br>NAME | BRITISH<br>COLUMBIA | MINISTRY OF<br>AND INF<br>SOUTH<br>HIGHWAY ENGIN | , ~<br>,          |         |            |
|----|-----|----------------|--|---|---------------------|--|-------------------|---------|------------|
| А  |     |                |  |   |                     |  |                   |         |            |
|    |     |                |  |   |                     |  | DESIGNED          | BK DATE | 2017-11-26 |
|    |     |                |  |   |                     |  | QUALITY CONTROL   | SM_DATE | 2017-11-26 |
|    |     |                |  |   | SENIOR DESIGNER     |  | QUALITY ASSURANCE | CP DATE | 2017-11-26 |
|    |     |                |  |   | DATE 2017-11-26     |  | DRAWN             | BK DATE | 2017-11-26 |


N/A

N/A

C0-200


| A

1




|              |          |          |          |         | +0.04% |         |         |         | <b>\</b> |        |
|--------------|----------|----------|----------|---------|--------|---------|---------|---------|----------|--------|
| ).50%        |          |          |          |         |        |         |         |         |          |        |
|              |          |          |          |         |        |         |         |         |          |        |
|              |          |          |          |         |        |         |         |         |          |        |
|              |          |          |          |         |        |         |         |         |          |        |
|              |          |          |          |         |        |         |         |         |          |        |
|              |          |          |          |         |        |         |         |         |          |        |
|              |          |          |          |         |        |         |         |         |          |        |
|              |          |          |          |         |        |         |         |         |          |        |
|              |          |          |          |         |        |         |         |         |          |        |
|              |          |          |          |         |        |         |         |         |          |        |
|              |          |          |          |         |        |         |         |         |          |        |
| 75 4 000 4 1 |          |          |          |         |        |         |         |         |          |        |
| 75 1+600 1+0 | 625 1+65 | 50 1+675 | 1+700 1+ | -725 1+ | 750 1+ | //5 1+8 | 800 1+8 | 325 1+8 | 850 1+8  | 375 1+ |
|              |          |          |          |         |        |         |         |         |          |        |

| SC. | ALE  | 0 10<br>0 1 | H 1:1000<br>V 1:100 | 50m<br>5m | CAD FILENAME<br>PLOT DATE | C0-200<br>4/10/2018 |                 | British<br>Columbia | AND INF | F TRANSPORTATIC<br>RASTRUCTURE<br>COAST REGION |
|-----|------|-------------|---------------------|-----------|---------------------------|---------------------|-----------------|---------------------|---------|--|
| REV | DATE |             | RE\                 | /ISIONS   |                           | NAME                |                 |                     |         | EERING AND GEOMATI                             |
| А   |      |             |                     |           |                           |                     |                 |                     |         |  |
|     |      |             |                     |           |                           |                     |                 |                     |         | DESIGNED                                       |
|     |      |             |                     |           |                           |                     | SENIOR DESIGNER | 2                   |         | QUALITY ASSURANCE                              |
|     |      |             |                     |           |                           |                     | DATE 2017-11    |                     |         | DRAWN  |




| DN TEI                           |             | 203                        |        |                |     |
|----------------------------------|-------------|----------------------------|--------|----------------|-----|
| ICS                              |             | CHANCELLOR BOUI<br>PROFILE | LEVARD | )              |     |
| <u>BK</u> DATE <u>2017-11-26</u> |             | STA. 1+440.000 TO 2+0      | 00.000 |                |     |
| <u>SM</u> DATE <u>2017-11-26</u> |             |                            |        |                |     |
| <u>CP</u> DATE <u>2017-11-26</u> | FILE NUMBER | PROJECT NUMBER             | REG    | DRAWING NUMBER | REV |
| <u>BK</u> DATE <u>2017-11-26</u> | N/A         | N/A                        | 1      | C0-200         | A   |






| Ş  | CALE | Ξ    | 0 1 1:100 5m | CAD FILENAME<br>PLOT DATE | <u>C0-300</u><br>4/10/2018 | COLUMBIA AND INF | TRANSPORTAT<br>RASTRUCTURE<br>COAST REGION | ~  |             | 301<br>CHANCELLOR BOU |     |                |     |
|----|------|------|--------------|---------------------------|----------------------------|------------------|--|--|-------------|-----------------------|-----|----------------|-----|
| RE | V    | DATE | REVISIONS    | Ν                         | NAME                       | HIGHWAY ENGIN    |  | DETAILS - CROSS-S                                      |             |                       |     |                |     |
| A  |      |      |              |                           | -                          |                  |  |  |             |                       |     | -              |     |
| Γ  |      |      |              |                           |                            |                  | DESIGNED                                   | BK DATE <u>2017-11-26</u><br>SM DATE <u>2017-11-26</u> |             |                       |     |                |     |
|    |      |      |              |                           | -                          | SENIOR DESIGNER  | QUALITY ASSURANCE                          | <u>CP</u> DATE <u>2017-11-26</u>                       | FILE NUMBER | PROJECT NUMBER        | REG | DRAWING NUMBER | REV |
|    |      |      |              |                           |                            | DATE 2017-11-26  | DRAWN                                      | KO DATE <u>2017-11-26</u>                              | N/A         | N/A                   | 1   | C0-300         | A   |



SO

) M, MIN. DEPTH OF RAIN ABOVE NATIVE S



FOOTING SUPPORTS FACING UNITS ONLY. -ASSUME 0.5 M WIDTH

#### MSE RETAINING WALL DETAIL SCALE 1:100

DRAINAGE FILL \_\_\_\_ (0.30 M)

|   | SCA | LE   | 0 2 1:250 | 12m   | CAD FILENAME<br>PLOT DATE | C0-300<br>4/10/2018 | BRITISH<br>COLUMBIA | AND INF | F TRANSPORTA<br>RASTRUCTUR<br>COAST REGION |        |
|---|-----|------|-----------|-------|---------------------------|---------------------|---------------------|---------|--|--------|
| R | EV  | DATE | REVIS     | SIONS |                           | NAME                |                     |         | EERING AND GEO                             | MATICS |
|   | А   |      |           |       |                           |                     |                     |         | DESIGNED                                   | BK     |
|   |     |      |           |       |                           |                     |                     |         | QUALITY CONTROL                            | SM     |
| Γ |     |      |           |       |                           |                     | SENIOR DESIGNER     |         | QUALITY ASSURANCE                          | CP     |
|   |     |      |           |       |                           |                     | DATE 2017-11-26     |         | DRAWN                                      | BK     |


LAYFIELD E-GRID 65R GEOGRID

OR APPROVED EQUIVALENT

5. COMPACTION: 95% OF STANDARD

PROCTOR


| N<br>S                          |             | 302<br>CHANCELLOR BOULE<br>DETAILS - WALL GEN<br>ARRANGEMENT | ERAI |                |     |
|---------------------------------|-------------|--|------|----------------|-----|
| K DATE <u>2017-11-26</u>        |             |  |      |                |     |
| M DATE                          |             |  |      |                |     |
| P DATE 2017-11-26               | FILE NUMBER | PROJECT NUMBER   | REG  | DRAWING NUMBER | REV |
| <u>K</u> DATE <u>2017-11-26</u> | N/A         | N/A  | 1    | C0-300         | Α   |




|                     | (MH2)                        |                |                          |                               | 3)               | M                | -14 |
|---------------------|------------------------------|----------------|--------------------------|-------------------------------|------------------|------------------|-----|
|                     |                              | EXISITING GROU |                          |                               |                  |                  |     |
|                     |                              |                |                          |                               | ~                |                  |     |
| ГМ - 79.89m @ 1.00% | 6                            | PR. 200Ø       | PVC STM - 76.26m @ 1.009 | %                             | PR. 200Ø PVC STM | - 38.90m @ 1.00% |     |
|                     | W INV 72.011<br>E INV 72.011 |                |                          | W INV 71.248<br>NE INV 71.248 |                  | SW INV 70.859    |     |
| 0+050               | 0+075                        | 0+100          | 0+125                    | 0+150                         | 0+17             | •                | 0+2 |


| sc  | ALE  | 0 5 H 1:500<br>0 0.5 V 1:50 | 25m CAD FILENAME<br>PLOT DATE<br>2.5m | <u>C0-600</u><br>4/10/2018 | BRITISH<br>COLUMBIA | AND INF | F TRANSPORTATI<br>TRASTRUCTURE<br>COAST REGION |
|-----|------|-----------------------------|---------------------------------------|----------------------------|---------------------|---------|--|
| REV | DATE | REVISI                      | ONS                                   | NAME                       |                     |         | EERING AND GEOMA                               |
| А   |      |                             |                                       |                            |                     |         | DECIONED                                       |
|     |      |                             |                                       |                            |                     |         |  |
|     |      |                             |                                       |                            |                     |         | QUALITY CONTROL                                |
|     |      |                             |                                       |                            | SENIOR DESIGNER     |         | DRAWN  |
|     |      |                             |                                       |                            | DATE 2017-11-26     |         | DRAWN  |


| BK DATE   |             |                |          |                                   |     |
|---|-------------|----------------|----------|-----------------------------------|-----|
| SM DATE 2017-11-26  |             |                |          |                                   |     |
| CP         DATE         2017-11-26           BK         DATE         2017-11-26 | FILE NUMBER | PROJECT NUMBER | REG<br>1 | drawing number<br>C0-600 -<br>601 | REV |
|   |             |                | · · · ·  |                                   |     |




|   | SCA | ALE  | 0 5 | H 1:500<br>V 1:50 | 25m<br><br>2.5m | CAD FILENAME<br>PLOT DATE | C0-600<br>4/10/2018 |                 | British<br>Olumbia | AND INF | F TRANSPORTATI<br>TRASTRUCTURE<br>COAST REGION |
|---|-----|------|-----|-------------------|-----------------|---------------------------|---------------------|-----------------|--------------------|---------|--|
| F | REV | DATE |     | R                 | EVISIONS        |                           | NAME                |                 |                    |         | EERING AND GEOMA                               |
|   | А   |      |     |                   |                 |                           |                     |                 |                    |         | DESIGNED                                       |
|   |     |      |     |                   |                 |                           |                     |                 |                    |         | QUALITY CONTROL                                |
|   |     |      |     |                   |                 |                           |                     | SENIOR DESIGNER |                    |         | QUALITY ASSURANCE                              |
|   |     |      |     |                   |                 |                           |                     | DATE 2017-11-26 |                    |         | DRAWN  |








| SCALE    | 0 1 1:100 5m CAD FILEN |      | COLUMBIA AND IN | F TRANSPORTA<br>FRASTRUCTURI<br>H COAST REGION | 4                                |             | S-101<br>CHANCELLOR BOUL          |         |                |     |
|----------|------------------------|------|-----------------|--|----------------------------------|-------------|-----------------------------------|---------|----------------|-----|
| REV DATE | REVISIONS              | NAME |                 | NEERING AND GEON                               | ATICS                            | D           | CORRIDOR REDE<br>EDESTRIAN UNDERP |         |                |     |
| А        |                        |      |                 | DESIGNED                                       | BK DATE                          |             |                                   | ASS FLA |                |     |
|          |                        |      |                 | QUALITY CONTROL                                | <u>SM</u> DATE <u>2017-11-26</u> |             | 1                                 |         |                |     |
|          |                        |      | SENIOR DESIGNER | QUALITY ASSURANCE                              | <u>CP</u> DATE <u>2017-11-26</u> | FILE NUMBER | PROJECT NUMBER                    | REG     | DRAWING NUMBER | REV |
|          |                        |      | DATE 2017-11-26 | DRAWN  | BK DATE2017-11-26                | N/A         | N/A                               |         | S-101          | A   |



## CAST-IN-PLACE PEDESTRIAN UNDERPASS TYPICAL SECTION SCALE 1:20



BACKFILL & LIGHTLY COMPACT w/ CLEAN,

15M HOOKED REINF. TO MATCH VERTICAL BARS IN WALL ALT. HOOKS. (CENTERED IN WALL)

LOOSE GRANULAR MATERIAL ONLY AFTER BOTH SLAB AND FLOOR FRAMING

IS IN PLACE & SHEATHING NAILED

| SC  | ALE  | CAD FILENAME<br>PLOT DATE | <u>C0-S100</u><br>4/10/2018 | BRITISH AND IN  | OF TRANSPORTATI<br>IFRASTRUCTURE<br>H COAST REGION |
|-----|------|---------------------------|-----------------------------|-----------------|--|
| REV | DATE | REVISIONS                 | NAME                        |                 | NEERING AND GEOMA                                  |
| А   |      |                           |                             |                 | DEGLONED   |
|     |      |                           |                             |                 | DESIGNED   |
|     |      |                           |                             | SENIOR DESIGNER | QUALITY ASSURANCE                                  |
|     |      |                           |                             | DATE 2017-11-26 | DRAWN  |

| ION TICS |            |             | S-102<br>CHANCELLOR BOULE<br>CORRIDOR REDES<br>PEDESTRIAN UNDER | GN<br>PAS |                    |     |
|----------|------------|-------------|---|-----------|--------------------|-----|
| BK DATE  | 2017-11-26 |             | TYPICAL DETAILS   | 5         |                    |     |
| SM DATE  | 2017-11-26 |             |   |           |                    |     |
| CP DATE  | 2017-11-26 | FILE NUMBER | PROJECT NUMBER  | REG       |                    | REV |
| BK DATE  | 2017-11-26 | N/A         | N/A   | 1         | C0-S100 -<br>S-102 | A   |

# TYPICAL SLAB ON GRADE CRACK CONTROL JOINT

SCALE 1:20

SAW-CUT CONTROL JOINT IN CONCRETE SLAB


FOOTING SIZES & REINFORCING.


FOOTING SCHEDULE FOR

SEE FOUNDATION PLAN AND

SEE FOUNDATION PLAN FOR SLAB THICKNESS.

TYP. <u>8" THK. CONC. FOUNDATION WALL REINF.:</u> 15M @ 18"oc. VERTICAL (CENTERED IN WALL) 15M @ 18"oc. HORIZONTAL (CENTERED IN WALL)





| SC  | ALE  | CAD FILENAME<br>PLOT DATE | <u>C0-S100</u><br>4/10/2018 | BRITISH<br>COLUMBIA | AND INF | F TRANSPORTATION<br>RASTRUCTURE<br>COAST REGION | 0  |
|-----|------|---------------------------|-----------------------------|---------------------|---------|---|----|
| REV | DATE | REVISIONS                 | NAME                        |                     |         | EERING AND GEOMAT                               | ٢I |
| А   |      |                           |                             |                     |         |   |    |
|     |      |                           |                             |                     |         | DESIGNED  |    |
|     |      |                           |                             |                     |         | QUALITY CONTROL                                 | 5  |
|     |      |                           |                             | SENIOR DESIGNER     | _       | QUALITY ASSURANCE                               |    |
|     |      |                           |                             | DATE 2017-11-26     |         | DRAWN   |    |
|     |      |                           |                             |                     |         |   | -  |

# SLAB REINFORCEMENT DETAIL

SCALE 1:10

| ON<br>TICS                               |             | S-103<br>CHANCELLOR BOULE<br>CORRIDOR REDES<br>PEDESTRIAN UNDER | GN<br>PAS | S              |     |
|--|-------------|---|-----------|----------------|-----|
| BK DATE 2017-11-26<br>SM DATE 2017-11-26 |             | REINFORCEMENT DE  | IAIL      | S              |     |
| <u>CP</u> DATE <u>2017-11-26</u>         | FILE NUMBER | PROJECT NUMBER  | REG       | DRAWING NUMBER | REV |
| BK DATE                                  | N/A         | N/A   | 1         | S-103          | Α   |