CANADIAN PACIFIC RAILWAY COMPANY

British Columbia Coast Steamship Service

PACIFIC REGION

DESCRIPTION OF PROJECT - 1970

GENERAL OVERHAUL REPAIRS

"PRINCESS OF VANCOUVER"

NECESSITY

To maintain vessel in operating condition.

ESTIMATE	LABOUR	MATERIAL	TOTAL
Drydocking -	$ 4,000	$ 500	$ 4,500
General overhaul and inspection repairs -	8,000	1,000	9,000
Cleaning and painting underwater surfaces -	5,000	1,500	6,500
Opening up boilers and machinery and underwater fittings for C.S.I. and Lloyds -	20,000		20,000
Bow propeller to be examined and repaired as required -	1,000	500	1,500
Railway trackage repairs and renewals as required -	2,500	500	3,000
Starboard Inboard Vulcan Fluid drive to dismantle, inspect and repair as required -	5,500	1,500	7,000
Port propeller shaft to be withdrawn for inspection for C.S.I. and Lloyds.	4,500	1,500	6,000
Electrolytic sea water protection repairs and renewals -	2,000	1,000	3,000
Supply 1,120 new type life jackets adult, and 112 life jackets for children, C.S.I. requirement -		8,000	8,000
Remodel Coffee Shop -	12,000	6,500	18,500
	$ 64,500	$ 22,500	$ 87,000

propeller shaft

9500
96,500

Office of Manager, Marine Operations
Vancouver, B. C.
July 28th, 1969.

C A N A D I A N P A C I F I C R A I L W A Y C O M P A N Y

British Columbia Coast Steamship Service

PACIFIC REGION

DESCRIPTION OF PROJECT - 1970

GENERAL OVERHAUL REPAIRS

"PRINCESS MARGUERITE"

NECESSITY

To maintain vessel in operating condition.

ESTIMATE	LABOUR	MATERIAL	TOTAL
Drydocking -	$ 3,000	$ 500	$ 3,500
Cleaning and painting underwater surfaces -	2,000	1,500	3,500
General overhaul and inspection repairs -	2,000	1,500	3,500
Opening up boilers and machinery and underwater fittings for C.S.I. and Lloyds -	20,000 ~~25,000~~		20,000 25,000
Electrolytic sea water protection repairs and renewals -	1,500	800	2,300
Repairs to ~~wood~~ decks -	3,000	1,500	4,500
Repairs to guard rail -	1,000	500	1,500
Starboard propeller shaft to be withdrawn for inspection -	5,000	500	5,500
Fore peak tank, 4 fresh water tanks, #1 double bottom tank, #2 double bottom tank, port & starboard, opened up for inspection & cleaned.	5,000	1,500	6,500
Hull and decks to be electronically gauged for Lloyds (requirements for a 20 year old vessel) -	1,000		1,000
Interior and exterior painting except underwater surfaces -	2,000	500	2,500
Retile galley deck, requested by health authorities -	4,000	2,500	6,500
Replacement linen -		2,000	2,000
	$ 54,500 49,500	$ 13,300	$ 67,800 62,800.

Office of Manager, Marine Operations
Vancouver, B. C.
July 28th, 1969.

C A N A D I A N P A C I F I C R A I L W A Y C O M P A N Y

British Columbia Coast Steamship Service

PACIFIC REGION

DESCRIPTION OF PROJECT - 1970

GENERAL OVERHAUL REPAIRS

"PRINCESS PATRICIA"

NECESSITY

To maintain vessel in operating condition.

ESTIMATE	LABOUR	MATERIAL	TOTAL
Drydocking -	$ 3,000	$ 500	$ 3,500
Cleaning and painting underwater surfaces -	2,000	1,500	3,500
Opening up boilers & machinery and underwater fittings for C.S.I. and Lloyds -	~~25~~ 15,000		~~25,000~~ 15,000
General overhaul and inspection repairs	2,000	1,500	3,500
(12) R.F.D. inflatable life rafts to be opened, inspected, tested and repacked -	2,000	1,600	3,600
Interior and exterior painting except underwater surfaces -	2,000	500	2,500
Bailey Board repairs and renewals -	500	250	750
Electrolytic sea water protection system repairs and renewals -	2,000	1,600	3,600
Port and starboard deep fresh water tanks No. 1 and No. 2 to be opened up, cleaned & inspected, also oil overflow tank -	5,000	1,500	6,500
Repairs to ~~[illegible]~~ decks -	3,000	1,500	4,500
Port propeller shaft to be withdrawn for inspection -	5,000	1,500	6,500
Air conditioning repairs & renewals -	1,000	500	1,500
Replacement linen -		7,500	7,500
RE INSULTATION 2 400KW generators	18000	~~[illegible]~~	10,000.
	$ 52,500	$ 19,900	$ 72,400

Office of Manager, Marine Operations
Vancouver, B. C.

July 28th, 1969.

C A N A D I A N P A C I F I C R A I L W A Y C O M P A N Y

British Columbia Coast Steamship Service

PACIFIC REGION

DESCRIPTION OF PROJECT - 1970

GENERAL OVERHAUL REPAIRS

"TRANSFER NO. 4"

NECESSITY

To maintain vessel in operating condition.

ESTIMATE	LABOUR	MATERIAL	TOTAL
General overhaul and inspection including drydocking and underwater painting.	$ 4,500	$ 1,500	$ 6,000

Office of Manager, Marine Operations,
Vancouver, B. C.,
July 28th, 1969.

C A N A D I A N P A C I F I C R A I L W A Y C O M P A N Y

British Columbia Coast Steamship Service

PACIFIC REGION

DESCRIPTION OF PROJECT - 1970

GENERAL OVERHAUL REPAIRS

"TRAILER PRINCESS"

NECESSITY

To maintain vessel in operating condition.

ESTIMATE	LABOUR	MATERIAL	TOTAL
Drydocking -	$ 3,500	$ 500	$ 4,000
Cleaning and painting underwater surfaces -	2,000	1,500	3,500
Exterior and interior cleaning and painting except underwater -	1,000	500	1,500
Bow propeller repairs -	1,000	500	1,500
General overhaul and inspection repairs -	8,500	1,500	10,000
Port and starboard propeller shafts to be withdrawn for inspection -	8,000	1,500	9,500
Electrolytic sea water protection repairs and renewals -	1,000	500	1,500
	$ 25,000	$ 6,500	$ 31,500

Office of Manager, Marine Operations
Vancouver, B. C.,
July 28th, 1969.